

N O T I C E

THIS DOCUMENT HAS BEEN REPRODUCED FROM
MICROFICHE. ALTHOUGH IT IS RECOGNIZED THAT
CERTAIN PORTIONS ARE ILLEGIBLE, IT IS BEING RELEASED
IN THE INTEREST OF MAKING AVAILABLE AS MUCH
INFORMATION AS POSSIBLE

DOE/NASA CONTRACTOR
REPORT

DOE/NASA CR-161803

SOLAR HEATING SYSTEM INSTALLED AT BELZ INVESTMENT
COMPANY, MEMPHIS, TENNESSEE - FINAL REPORT

Prepared from documents furnished by

Belz Investment Company
5118 Park Avenue
Memphis, Tennessee 38117

Under Contract DOE EM-78-F-01-5210

Monitored by

National Aeronautics and Space Administration
George C. Marshall Space Flight Center, Alabama 35812

For the U. S. Department of Energy



(NASA-CR-161803) SOLAR HEATING SYSTEM
INSTALLED AT BELZ INVESTMENT COMPANY,
MEMPHIS, TENNESSEE Final Report (Belz
Investment Co.) 100 p HC A05/MF A01

N81-28521

Unclass

CSCL 10A G3/44 26996

U.S. Department of Energy



Solar Energy

TABLE OF CONTENTS

Solar System Description	1
System Start Up and Acceptance Test Results.	8
Collector Technical Data10
Collector Installation Manual.15
Air Handler Installation Manual.32
Heat Storage Unit Installation Manual.49
System Owner's Manual for Operation and Maintenance.70
As Built Drawings.93

PRECEDING PAGE BLANK NOT FILMED

SOLAR SYSTEM DESCRIPTION

SHELBY OAKS CORPORATE PARK
QUAT IV COMPLEX

5710 Summer Trees Drive
Memphis, Tennessee 38138

Application	Solar heating for 4 separate buildings
System Type	Active hot air
Collector Type	Flat plate air
Collector Manufacturer	Solaron Corporation
Collector Area	780 square feet/bldg.
Storage Capacity	390 cubic feet/bldg.
Building Load	99.23 x 10 ⁶ BTU/year without any credit for internal load/bldg.
BTU's Produced	60.15 x 10 ⁶ BTU/year/bldg.
Building Owner	Belz Investment Co. 5118 Park Avenue Memphis, TN 38117
Building Name	Shelby Oaks Office Complex Quad IV
Architect and Engineer	McFarland & Associates 5763 Summer Trees Drive Memphis, TN
Designer	Alfred M. Alperin A. T. Distributors Memphis, TN
Mechanical Contractor	Stephen's Brothers 2222 York Memphis, TN
General Contractor	Angel Contractors, Inc. 505 Perkins Road Memphis, TN 38117

This new building was built as a speculative office complex with 4 identical buildings around a landscaped courtyard. The setting is a tree studded flat lot between Highway 64 and I-40 with one story office and warehouse units near and a two story large office complex approximately one block to the east. The trees are deciduous.

The structure is on a concrete slab with heated space of approximately 6430 sq. ft. per building. Perimeter walls, with insulated bronze glass areas, are constructed with 1/2" gyp board, metal studs, batt insulation, exterior grade plywood, and aggregate panels. Roof insulation and all considerations of construction were to comply with ASHRAE 90-75, to minimize heat loss and heat gain.

Each building heat storage is within a concrete vessel built as part of the structure, insulated internally with 1 1/2 inch rigid insulation board,

six pound density fiberglass. This storage facility is located below the collectors on the building concrete slab at one end within the building perimeter.

Included, in the mechanical system of each building, is a Carrier Roof-top Cooling Unit connected to a system of supply sheet metal ducts and to Carrier Moduline Variable Volume Units.

Heating via the solar system and electric duct heaters are through the same sheet metal perimeter duct system, air handling unit and perimeter diffusers, for each building.

Design Philosophy

As heating systems in the area are generally of the hot air type distributed via a ducted system with cooling, most of the installing mechanics are trained to install sheet metal. Therefore, a hot air solar system seemed a natural for this building.

Flat plate air collectors, more particularly, Solaron Corporation collectors, were chosen by the designer, with the Architects' permission, for the following reasons:

- (a) The designer has been trained in Solaron's design and installation techniques.
- (b) The designer honestly believes the end user, in this case, is best served by solar air systems with a quality collector, properly installed. The problems of maintenance, deterioration, freeze-up, stagnation and control failure are minimized.
- (c) In the opinion of the designer, equal or more BTU's are delivered to the space by Solaron air systems. They usually begin collecting usable energy earlier in the day and can continue doing so until later in the day. Heated air is taken directly into the space with no additional heat transfer loss, and stratification of usable heat is better in rocks than in liquid storage.
- (d) As there was no need for high temperature, there was no consideration of concentrating or tracking collectors.

Solar hot water was not included as office buildings use so little hot water; it was not considered economically feasible.

Operation of the System

A Solaron air system has a special air handling unit to move air through the collectors and into and out of the rock storage, with connection to the air duct distribution system. The motor has Class B insulation on the windings to prevent deterioration as hot air passes over it. The heat of this motor is added to the heat delivered to the system.

Four motorized special low-leakage dampers and two gravity-fabric dampers are also part of the system.

The system is designed to be automatically controlled by a Solaron-provided solid state controller with three thermistors - one located in the collectors, one in the rock box top plenum, one in the return air duct from the heated space. A three stage heating thermostat located in the conditioned space controls the operation.

Modes of Operation are:

- 1) Heating the space from the collectors.
- 2) Storing heat in the rock storage.
- 3) Heating from storage.
- 4) Storing heat in the rock storage and air conditioning the conditioned space, as the air conditioning is a separate system.
- 5) Solar system off while providing air conditioning to the conditioned space.
- 6) Solar system off while providing conventional heating to the conditioned space.

If solar heat is insufficient to maintain space temperature, the electric heat backup system can come into operation in conjunction with modes one and three, thereby taking advantage of any solar BTU's available for the space.

As a three-stage heating thermostat controls the perimeter temperature, backup heat can only be energized by the thermostat's second stage for the electric heat's first stage, and the third stage of thermostat operates the second stage of the electric heat. A time clock is provided to operate night set-back.

The first building was completed in the fall of 1979, and the solar system operated during the winters of 79-81, for the north building, and for the south and east building for 80-81. The west building is now in operation. In the closet adjacent to the rock storage, a panel was fabricated by the contractor. It has indicating lights for the mode the system is in, as well as the seven day program clock, and perimeter electronic thermostat set point controllers.

Problems Encountered and Solutions

- (A) At the design review with DOE representatives, construction details were reviewed and all major parts of the solar system were scrutinized and any indecisions were cleared up.
- (B) However, when the steel supports were detailed and fabricated by the steel erectors, the smooth surface needed for the collectors was not adhered to and the steel had to be reworked. Also, the hole punching for the collector hold down bolts was not always aligned correctly, so some field corrections were made.
- (C) As the installation of the collectors was new to the installing contractor's personnel, the collector supplier supervised the first few to alleviate any fears they might have, and afterwards the collector installation was accomplished very smoothly.

- (D) The inside glass of the double glazed cover of one collector shattered after installation (several weeks later), but the installer decided to wait until the building was to be occupied to see if anyone noticed the solar system. He received numerous calls indicating the public really was watching the job.


The cause of the glass to shatter was never determined, but it was suspected that it expanded with heat from the collector and the tempering was defective.

- (E) After check out, the fan motors all had to be increased one size and the fans speeded up to produce enough air on the perimeter.
- (F) One fan wheel disintegrated and had to be replaced. Two fan motor bases came loose.
- (G) Some trees need to be trimmed to reduce shadowing in mid-winter of some of the collectors.
- (H) The steel supports for the collectors are probably of heavier construction than absolutely necessary. However, no leaks or movement has been detected. In future jobs, this support should be studied to see if it can be reduced in cost.

Costs

Prior to submission of the application to DOE, a substantial set of mechanical plans of the solar system was developed and priced by Stephens' Brothers. However, the collector penthouses and steel supports cost the owner more than was anticipated.

The cost of the system for four buildings, including architectural and engineering fees, was approximately \$159,880.00.




LOCATION PLAN

ORIGINAL PAGE IS
OF POOR QUALITY

The following photograph shows the Build. 2 collectors. The owner has permission from adjacent property owner to remove or trim trees that will provide winter shading of the building. It should be noted that the vast majority of the trees on the property are deciduous.

ORIGINAL PAGE IS
OF POOR QUALITY




Building 2 Solar Collector (Air)

ALL ORIGINAL PAGE IS
OF POOR QUALITY

SYSTEM START UP
AND
ACCEPTANCE TEST RESULTS

S.O.L.A.R. 1900.00.004W
Replaces 1900.00.003W

SYSTEM START-UP



PROJECT NAME: Shelby Oaks - Quad IV DATE: _____
PROJECT TYPE: RES'L _____ COMM'L X IND'L _____
AGRI _____ OTHER: _____
LOCATION: South Building (Typical)
COLLECTOR ARRAY: 2 HIGH X 20 WIDE = 780 SQ. F
SERVICEMAN: Bysse - Hughes
COMPANY: Stephens Bros - H. T. Dist
PHONE: () _____

SOLAR HEATING FLOW SCHEMATIC

SEQUENCE OF OPERATIONS									
MODE	MD-1	MD-2	BD-1	BD-2	MD-3	MD-4	SOLAR PUMP	HEATER	RESTART
HEATING FROM COLLECTOR	O	C	O	O	C	O	ON	OFF	
HEATING FROM STORAGE	C	C	O	C	O	O	ON	OFF	
STORING HEAT	O	O	C	O	C	C	ON	OFF	
HEATING WITH FURNACE	C	O	O	C	C	O	ON	ON	

	AIR HANDLE	
	SOLAR	AL
Design CFM	<u>2000</u>	
Design Ext SP	<u>0.65</u>	
Fan RPM	<u>1040</u>	
HP	<u>1</u>	
Motor RPM	<u>1750</u>	
Volt	<u>115</u>	
Phase	<u>1</u>	
FLA	<u>14.6</u>	
SF	<u>1.25</u>	
SFA	<u>18.25</u>	
Insul. Class	<u>B</u>	
Motor Mfg	<u>G.E.</u>	
Model No.	<u>5KC81T</u>	

T₁ = 122°F
T₂ = 68°F
T₃ = 122°F

TEMPERATURE & STATIC PRESSURE MEASUREMENTS

STORING HEAT				HEATING FROM STORAGE				HEATING FROM COLLECTOR			
POINT	°F	STATIC PRESSURE	S.P. DIFF.	POINT	°F	STATIC PRESSURE	S.P. DIFF.	POINT	°F	STATIC PRESSURE	S.P. DIFF.
1		0.00		1	122	0.03		1	127	-0.05	
2	127	-0.31	0.67	2		0.00		2	127	-0.07	0.
3	127	+0.36	0.21	3	122	-0.05	0.11	3	122	0.00	
4	68	+0.15		4	68	-0.16		4	68	0.00	
5	66	-0.09	0.15	5		0.00	0	5	68	-0.07	
6	127	0.24		6		0.00		6	127	-0.22	0.
7				7	122	+0.21		7	127	+0.22	
8				8				8			

ORIGINAL PAGE IS
OF POOR QUALITY

COLLECTOR

TECHNICAL

DATA



TECHNICAL DATA

Series 2000

Air Type Solar Collector

PATENTS PENDING

The Solaron series 2000 flat plate air type collector represents the most advanced technology and manufacturing know-how available today in the solar heating field. The collector is based on over thirty years of research and testing and has proven highly efficient, reliable and maintenance free.

The collectors are completely factory pre-assembled to minimize field installation time and assure uniform quality and performance. The exclusive port and manifold system allows the collectors to be simply butted together and bolted in place. No field fittings are required between collectors.

The Solaron series 2000 collector is universal in application. Substantial energy savings can be realized in commercial, industrial and residential applications such as:

- MAKEUP AND FORCED AIR HEATING
- HYDRONIC SPACE HEATING
- DOMESTIC HOT WATER HEATING
- PROCESS HOT WATER APPLICATIONS
- PROCESS HOT AIR DRYING APPLICATIONS

The Solaron System can be used where application temperatures can be satisfied directly by the collectors as well as where the collectors are used to preheat air or water for high temperature applications.

The Solaron series 2000 collector conforms to the interim performance standards established by the Energy Research and Development Administration for solar collectors. These standards include:

- RESISTANCE TO HAIL, WIND FLUTTERING AND WIND LOAD.
- FREEDOM FROM FREEZING, CORROSION, AND OUTGASSING.
- RESISTANCE TO THERMAL AND SOLAR DEGRADATION.
- CONFORMITY TO NATIONAL SAFETY AND FIRE CODES.

FEATURES

- The Solaron series 2000 air type collector can be used in hydronic applications through the use of a high efficiency air to water heat exchanger. Since the collector uses air as the transfer medium, costly field piping, maintenance and wear are reduced or eliminated.
- Attractive appearance allows for architecturally pleasing applications, including construction of entire roofs and wall sections with solar panels.
- Factory preassembly includes insulation, manifold and glazing to eliminate field assembly.
- Simple installation system includes all hold down hardware and cap strip necessary for a complete installation. Perimeter flashing, typically field measured is provided by the builder.

CONSTRUCTION


The series 2000 collector module, designed for high efficiency and ease of installation, is constructed of the following materials:

- PAN - 20 gauge steel, fully insulated with 3-3/4" fiberglass batt. Painted external surfaces.
- GLAZING - Two 1/8" sealed special low iron tempered glass panels with long life EPDM perimeter gasket. Plates can be easily removed for service or replacement.
- ABSORBER - 28 gauge steel with porcelain enamel coating.
- CAP STRIP - Painted steel. Designed to assure weather seal between modules.
- CONNECTION PORTS - Unique flange configuration permits tight air seal automatically as modules are installed.


PERFORMANCE

- EFFICIENCY - collector efficiency is as high as 64.5% as a function of outlet minus ambient temperature over solar insolation. Where $T_{out} - T_{amb}$ equals 120° and insolation equals 300 BTU's per hour per square foot, a typical operating environment, the Solaron series 2000 collector efficiency exceeds that of flat plate liquid type collector.
- REFLECTANCE - the total reflectance of the absorber surface averages only about 5%.
- COVER TRANSMITTANCE - the transmittance of the two plate, low iron tempered glass cover is 80 percent from a 0 to 48 degree angle of solar incidence.
- HEAT DELIVERY - the excellent heat delivery characteristics of the Solaron series 2000 collector are shown on Figure 3.


MEASURED* COLLECTOR PERFORMANCE DATA




A—Collector efficiency as a function of outlet minus ambient temperature over insolation.




B—Collector efficiency as function of outdoor temperature for various solar inputs.



C—Collector heat delivery as a function of outdoor temperature for various solar inputs.



D—Effect of collector orientation on total system performance of a typical installation at 35° N latitude (J. D. Balcomb, J. C. Hedstrom, B. T. Rogers "Design Considerations of Air Cooled Collector/Rock-Bin Storage Solar Heating Systems," presented at 1975 ISES Los Angeles Meeting, Aug. 1975)



E—Effect of collector tilt on total system performance for a typical installation at 35° N latitude (J. D. Balcomb, J. C. Hedstrom, B. T. Rogers "Design Considerations of Air Cooled Collector/Rock-Bin Storage Solar Heating Systems," presented at 1975 ISES Los Angeles Meeting, Aug. 1975)

CORRECTIONS FOR NON-OPTIMUM ORIENTATION & TILT

Example: Project at 40° N. Latitude, 500 Ft² Coll. Area


1. If Orientation is 20° to the West
The relative collector area required to provide the same annual fuel savings as a system at due South is approximately 1.04 times the calculated collector area. Therefore, if the calculated collector area is 500 Ft² at due South, (1.04) (500) = 520 Ft² would be required at 20° West (or 500 Ft² could be used with the understanding that there will be a 4% loss in performance from the optimum due South.)

2. The optimum collector tilt would be 45° to 55° (i.e. L+5° to L+15°)
If the collectors were at a tilt of 35° (i.e. L-5°) the relative collector area required would be 1.03X500 Ft² = 515 Ft². If both conditions exist (i.e. 20° West & 35° tilt) the correction would be (1.04) (1.03) (500) = 535.6 Ft²

*Measured according to the guidelines set forth in ASHRAE proposed standard 93-P (Jan. 15, 1977) "Methods of Testing to Determine the Thermal Performance of Solar Collectors"

TYPICAL COLLECTOR INSTALLATION

ORIGINAL PAGE IS
OF POOR QUALITY



The Solaron series 2000 solar collector can be installed in either a horizontal or vertical position. Installation can be efficiently accomplished by a two-man crew. No special tools or installation techniques are required.

The optimal air flow rate through the collector is 2 SCFM/ft.². The design static pressure is 0.23" when the collectors are ducted as shown above.

On a special order basis, Solaron can provide collectors with precut manifold openings and manifold ports omitted where specified to further reduce field installation time.

Solaron Corporation provides mechanical engineering and field services to assist the local engineer and HVAC contractor in design and installation.


For additional information on the Solaron collector and related Air Handling and Automatic Control systems, contact Solaron Corporation Marketing Services.

SOLARON CORPORATION, MARKETING SERVICES

300 GALLERIA TOWER, 720 SO. COLORADO BLVD., DENVER, COLORADO 80222

303-759-0101

SOLARON COLLECTOR PANEL DETAILS



COLLECTOR PANEL

NOTE


THE SERIES 2000 COLLECTOR IS AVAILABLE IN 4 MODELS:

2001 - Std. for 2 panels HIGH

2002 - Special order for ANY Array

2003 - Std. for 1 panel HIGH

2004 Center panel of 3 HIGH Array



2003



2001



2001

2004

2001

COLLECTOR PANELS MAY ALSO BE GROUPED IN HORIZONTAL CONFIGURATION

The Solaron series 2000 collector is flexible in application. The modules can be installed on a roof section, wall section or free standing roof frame.

The collectors are installed as shown in the mounting system details above. Return and supply air is provided by simply installing a standard starting collar on the bottom of the collector anywhere within the 29" x 36" manifold area; thus collars can easily be located to clear roof trusses or wall studs. Perimeter flashing is field measured and installed to complete the system.

Other product information:

COLLECTOR WEIGHT - 153 pounds

INSTALLED DIMENSIONS - 36" x 78", center to center

PORT NET FREE AREA - 26.7 square inches each

PORT END CAPS & PORT GASKETS - provided by Solaron as required

COLLECTOR
INSTALLATION
MANUAL


INSTALLATION

S.O.L.A.R. 700.00.100

Revision 1


3-77

Series 2000 COLLECTOR PANELS




Collectors must be
stored in dry area

ION MANUAL



SOLARON™

SOLAR ENERGY SYSTEMS
720 S COLORADO BLVD
DENVER COLORADO 80222
303/759-0101




DWG. 1 STARTING PANELS SUPPORT STRIP

STEP #1

The builder and/or framer must install the roofing felt and the 1-1/2" x 1-1/2" starter strip at the bottom edge of the collector array as shown above, BEFORE any collector panel installation is started. This strip serves as support for bottom row of collectors until hold downs are installed and also is used to ensure proper alignment of the entire collector array. The collector array must be laid out so that it will fit on the roof with 6" clear on all sides for cap strip support and perimeter insulation. (see Drawing #2). Do not install 1-1/2" x 7-1/8" perimeter frame prior to collector mounting.

RECOMMENDED TOOL LIST

1/4" or 3/8" reversible, variable speed electric drill, sabre saw, reciprocating saw or skill saw, medium slot-type screw driver, 50 ft. or longer tape measure, 10 ft. to 16 ft. tape, chalk line, square (18"x24"), 2-7/16" hex sockets for 1/4" driver, two 1/4" x 6" extensions (to be mounted in drill chuck), utility knife, pliers (standard), Solaron pull-up tool (limited application), come-along with 30' min. cable length, sunglasses (polarizing), work gloves, safety helmets, safety ropes & accessories (if needed), ladders (appropriate for height of array being worked on), roof jacks (if required), machine for lifting collector onto roof (crane, front loader, etc.), matches or cigarette lighter, caulk gun, left & right snips, scratch awl, 5/16" dia. drill bit 10" long, Scribe.



DWG. 2 ARRAY LAYOUT ON ROOF

STEP #2

Chalk outline of actual perimeter of the collector array onto the roofing felt, as shown above, making certain that your lines are square and plumb.

STEP #3

From plan of collector array (mech. drawing) determine location of holes to be cut in sheathing. These holes permit access for starting collar connection between panel and duct work (see drawing #3 & #5). The holes in the collector panels can only be cut in the manifold section as shown in drawings 3 and 5. This must be coordinated with roof sheathing holes. Cut roof sheathing holes 2" in diameter larger than collar (i.e. plans show an 8" collar, cut a 10" hole. Hole may be either round or square.


NOTE

TILT PANEL TO ALLOW ACCESS FOR CUTTING HOLE IN BOTTOM (DUCT CONNECTION). DO NOT INVERT PANEL. GLASS IS NOT CLAMPED IN PLACE AND COULD DROP FROM FRAME WITH IMPROPER HANDLING

LAY BEAD OF DOW-CORNING CAULKING NO. 732-CL-11 UNDER COLLAR FLANGE FOR AIRTIGHT SEAL

SEE COLLECTOR ARRAY PLAN (MECH. PLAN) FOR HOLE SIZE

STARTING COLLAR (W FLANGE) FOR FLEX. DUCT CONN. MUST BE INSULATION GUARD TYPE (COLLAR EXTENDS 1" INTO PANEL)




DWG. 3 CUTTING OF COLLAR HOLE (method 4a)

STEP #4

Collar holes to be cut in the collector panels by one of two methods as follows:

- (a) Should the location of the mounted panel prevent easy access for hole cutting use method shown above for cutting hole before the collector panel is mounted to the roof sheathing. Make sure the hole you cut in the bottom of the panel and through insulation lines up with hole already cut in the roof sheathing.
- (b) After collectors are installed securely on the roof (as per Step #5) cut the required holes in the bottom of each predetermined collector panel (confirm the size & location of each hole with the mechanical plans).


Any method of collar mounting requires caulking with Dow-Corning #732-CL-11 to form air-tight joint between collar flange and the collector.



DWG. 4 HOLD-DOWN HARDWARE INSTALLATION

STEP #5

Referring to drawings 4 and 5, drill 5/16" holes in roof sheathing for collector hold downs in designated places, as shown in drawing 5. Secure exterior hold downs after collector is in place. When two panels are mated, drill 5/16" holes for the interior hold downs after the adjoining collector is pulled tightly against the port gasket. The gasket must be kept clean and applied to a clean surface.



DWG. 5 HOLD-DOWN HARDWARE ATTACHMENT POINTS

STEP #5 (Cont.)


Place each bolt with clamp into its proper hole (external hardware around the perimeter and internal hardware between collector panels - see drawing 4). One person must put a washer and a lock nut onto the same bolt from the attic side of the roof and tighten. A 7/16" socket & 7/16" open end wrench or adjustable wrench is recommended for tightening hold down bolts. Internal hold down should "dimple" collector metal. Exterior hold down should catch rivet. Should the location of the collector place the hold down bolt directly over a structural member you have two methods of mounting. 1) Discard the 6" x 1/4" bolt and use a 6" x 1/4" lag bolt. Tighten directly into the structural member. 2) Discard the 6" x 1/4" bolt and drill a 5/16" hole all of the way through the structural member. Use 1/4" all-thread to the required length and mount as described above. CAUTION - be sure the structural integrity of a member is not affected by this method of mounting BEFORE you start drilling.


Lag Hold-Downs

Place the hold down hardware (i.e. 6" X 1/4" lag bolt with the appropriate interior or exterior clamp) at the attachment points shown in drawing 5. Screw the lag bolt into the roof sheathing by using a 7/16" hex socket (on a 1/4" extension) and a 1/4" or 3/8" electric drill. Interior hold down clamps must dimple the collector metal to hold properly. Exterior clamps should catch one of the rivet heads on the collector. After lags have been drilled into place, a washer and tinnerman must be placed on the tip of lag from the underside of the roof.

Screw Hold-Downs

After placing collector in position, secure in place using 4 lag bolts or bolts. Using bugle-head drywall screws (2 3/8" #S12 or 6-20 X 1 5/16" flooring screws) drill into the backside of the collector and roof sheathing from the attic area. Eight (8) screws are required; four on each side near the edge of the collector. This procedure is recommended for very steep roof angles. DO NOT use sheetmetal screws for this application. Eight washers are also required and should be placed on the screw before drilling.





DWG. 6 PORT CONNECTIONS

STEP #6


Install the silicone gasket and attach end cap with screws to the collector panel, as shown above, making sure you obtain an airtight seal. As each panel is positioned in its location be sure that the gasket has been properly mounted around each port that will be immediately mated to an adjacent collector panel port. The gasket must seat evenly around the port to insure an airtight seal.

STEP #7

Lay a bead of Dow-Corning #732-CL-11 caulking compound around the opening in the bottom of the collector panel as shown in Drawing 3. This is to insure an airtight seal between the collector and the starting collar flange. Mount the starting collar in such a manner that will make a solid, airtight connection.

STEP #8 Relief Tube -


When collector is in place and secured, but before cap strip is installed, check red nylon pressure relief tube to make sure it is open so that pressure between panes of glass has had time to equalize to local atmospheric pressure. Next, seal tube by tying knot in tube and permanently sealing end by melting and squeezing the open end closed. Now place closed tube under neoprene gasket along the edge of the glass (see detail on dwg 6) & return gasket to normal position.



DWG. 7 CAP STRIP ASSEMBLY

STEP #9


After all the collectors are in place and secured, coordinate with builder to install 1-1/2" x 7-1/8" frame assembly around perimeter of array as per drawings 8 and 9 (mounting cap strip and flashing). Flashing must be installed before perimeter sealant and perimeter cap strip can be installed.



STEP #10

Referring to Drawings 7 & 8 start installation of cap strip. Cap strip is mounted with 2-1/2" screws and metal backed neoprene washer. Place screw with washer through pre-drilled holes in cap strip. See Drawing 7. Turn the screw into the tinnerman clip approximately 3 turns. Place cap strip so that each edge is lined up on collector glass gasket evenly with nut plates under glass enclosure lip. By pressing on the screw while turning to secure nut plate, you will keep nut plate straight so that it will secure itself under adjacent glass enclosure shelves. Cap strips between collectors should be mounted during collector installation to hold glass in place.

NOTE: Wood Frame Ass'y. ($1\frac{1}{2} \times 7\frac{1}{8}$ " plus Plywd. Strip) To Be Installed After Collector Panels Are In Place



COLLECTOR FLASHING/SENSOR PLACEMENT


STEP #11

When you install the perimeter cap strip, the same procedure is followed, except that you will be placing one edge of cap strip on glass gasket and the other edge into the perimeter flashing sealant (See drawing 9). Flashing sealant is placed on flashing prior to cap strip mounting.

STEP #12

When installing the "Cross, El or Tee" cover plates, run a double bead of Dow-Corning 732-CL-11 silicone caulk on the cap strip as shown in Drawing 8. Install $\frac{5}{8}$ " Tec self-drilling screws in pre-drilled holes and tap into cap strip. A third hole must be drilled into the 90 degree L in accordance with the wood backing to obtain a tight seal in the corners (see Drawing 8).

NOTE: $2\frac{1}{2}$ " screws, metal backed neoprene washers, nut-plate and tinnermans & $\frac{5}{8}$ " self-tapping screws furnished by Solaron.




DWG. 10 ASSEMBLY DETAILS

1 HIGH

VERTICAL ARRAY

(2003 "X" and "Y" PANELS)



SEE INSTALLATION MANUAL
FOR ADDITIONAL INSTRUCTIONS

3 HIGH


VERTICAL ARRAY

END CAP PAIR-TYPICAL
TO CLOSE OFF OUTSIDE
PORTS-PERIMETER OF
COLLECTOR ARRAY. SEE
PAGES 6,10, INSTALL-
ATION MANUAL

PORT GASKETS
BETWEEN ALL
INTERIOR PORT
CONNECTIONS. SEE
PAGES 6,10, INSTALL-
ATION MANUAL

HOLE CUT IN PANEL AND
SHEATHING FOR COLLAR
(PAGE 3, INSTALL. MANUAL)

HOT AIR FROM
COLLECTOR




SEE INSTALLATION MANUAL
FOR ADDITIONAL INSTRUCTIONS

1 HIGH

HORIZONTAL ARRAY

(2001 PANEL)




SEE INSTALLATION MANUAL
FOR ADDITIONAL INSTRUCTIONS

3 HIGH

HORIZONTAL ARRAY

(2001 PANEL)



SEE INSTALLATION MANUAL
FOR ADDITIONAL INSTRUCTIONS


AIR HANDLER
INSTALLATION
MANUAL

INSTALLATION

S.O.L.A.R. 900.40.050

6-1977

INLET



SERIES
AU0400
&
AU0500
AIR
HANDLER

TM
Solaron Corporation reserves the right to make changes at any time, without notice, in materials, equipment, specifications, prices, models and design criteria, and to discontinue models.



ION MANUAL

SOLARON AU0400 AIR HANDLING UNIT

Solaron's model AU0400 series air handler units are shipped less motor and internal wiring to facilitate installation in a wide variety of applications. All AU0400 series units are manufactured with highly reliable belt drive type blowers. Motors are to be field installed to match each installation's air delivery requirements. Compatible motors are 1/3, 1/2 & 3/4 H.P. of 115 or 230 volt power input. Class "B" insulation types of motors are required for use in the AU0400 units due to the higher operating temperatures typical of an air-type solar heating system. All units have a factory mounted "J" box for convenient line voltage field wiring.

WARNING: Do not install the AU0400 unit in a corrosive, explosive or contaminated atmosphere for any reason. Installation of this unit is subject to all applicable local and national building codes and ordinances.

The Solaron AU0400 may be mounted in several positions. Any mounting position must result in the blower shaft being in a horizontal position (i.e. parallel to the floor). DO NOT MOUNT in a position that places the blower shaft in a vertical orientation.

The AU0400 may be suspended from ceiling joists, wall-mounted or floor mounted. Provide adequate vibrations isolators to insure quiet operation.


NOTE: The AU0400 contains no electric heating coils or gas-fired exchangers that produce inherently high temperatures.

REQUIRED DAMPER MOUNTING

Mounting the Solaron dampers on the inlet and outlet of the AU0400 air handler is easily accomplished if the steps listed below are followed:

1. If the system incorporates the optional domestic water preheating, mount the water coil assembly to the inlet of the AU0400 unit using sheet metal screws. (If the inlet is to be on the end of the AHU, an opening must be field cut). Next, mount damper MD1 onto the mounting flange of the water coil assembly.
2. Position and mount with sheetmetal screws damper MD1 (inlet from collector "normally closed") over the opening on the inlet of the air handler, or water coil if used. Dampers are labeled to indicate direction of air flow and must be installed accordingly.
3. Position and mount with sheetmetal screws damper MD2 (outlet to auxiliary heating unit "normally open") over one of the openings on the outlet of the air handler. Field cutting may be required.
4. Position and mount the field supplied duct over one of the other openings on the outlet of the air handler going to the top of the heat storage bin.

NOTE: The damper motor must be mounted in a position that results in the output shaft of the damper motor being in a horizontal position (i.e., damper blades must be parallel to the floor). All joints must be sealed air-tight with silicone caulking.





Model No.	DAMPERS DOM. WATER COIL			
	A	B	C	D
AU-0400	16"	16"	8"	6"
AU-0500	20"	20"	10"	6"

TWO COVER PANELS ARE WITH UNIT. ADDITIONAL PANELS MUST BE FIELD FABRICATED.

AU-0400 AND AU-0500 AIR HANDLING UNITS

DIMENSIONAL INFORMATION

The above drawing will furnish orientation information as well as essential dimensional data.




DIMENSIONS

UNIT	A	B	C	D	E	F
AU-0400	42	20	18	14	7	10
AU-0500	51	24	22	18	8	11



BOTTOM



NOTES

INLETS

- A₁ FACTORY CUT (DO NOT USE)
- A₂ FIELD CUT (RECOMMENDED)
- A₃ FIELD CUT (8% FAN CAPACITY REDUCTION)

OUTLETS

- B₁ FACTORY CUT (STANDARD)
- B₂ FIELD CUT (OPTION)
- C SERVICE ACCESS

FOR MOTOR AND DRIVE REMOVAL

AUO400 & AUO500 AIR HANDLING UNIT

Locate the filter "upstream" of backdraft damper BD-1 (and "by-pass" duct when used).

FILTERS

The Solaron air system requires a filter in the return air duct supplying air to the inlet side of the collector and the heat storage bin. A filter is not needed in the AU0400/AU0500 unit.

Should an electronic air cleaner be desired, install it in the return air duct mentioned above. DO NOT install on the inlet of the auxiliary furnace as the air temperatures at this location may exceed the electronic air cleaner's maximum operating temperature (usually 125°F).

HUMIDIFIERS

Horizontally mounted type humidifiers are recommended. Locating the humidifier in a horizontal supply duct coming off of the auxiliary heating unit is ideal. Utilizing a sail-switch activated duct humidistat (similar to a Honeywell H49B) will simplify the wiring requirements of most installations.

DO NOT wire low voltage humidifiers or air cleaner relays in series with the thermostat wires (W₁ or W₂) as this can damage the Solaron controller. Sail or air pressure switches are recommended.

LOCATING THE THERMOSTAT

The Solaron multi-element thermostat should be located on an interior wall free from cold and warm drafts. Be sure adequate room air movement is present so the thermostat will provide a comfortable building temperature.

Do not locate the thermostat near lamps, heat outlets, stoves, refrigerators, television sets, etc. The heat given off by these appliances will not allow the thermostat to properly control the building temperature.

The thermostat heat anticipators should be set as follows: W₁ @ .10 amp, W₂ @ .10 amp.

SOLARON CONTROLLER & THERMOSTAT LIST

AU0400 and AU0500 air handler can be used in various applications.

Application	Solaron Controller	Thermostat & Sub-base	Additional Relays Needed
Heating Only	HC0115	HC0020 HC0040	(3)#SR0225 Relays 1-AU0400 Blower 1-Dom. Water Pump 1-Aux. Blower
Heating Only with continuous fan option	HC0115	HC0020 HC0041	(3)#SR0225 Relays Same as Above *(1)#SR0157 Relay
Heating/cooling with continuous fan option	HC0115	HC0022 HC0041	(3)#SR0225 Relays Same as Above *(1)#SR0157 Relay
Heat pump-reversing valve energized for heating	HC0116	HC0022 HC0042	(2)#SR0225 Relays 1-AU0400 Blower 1-Dom Water Pump
Heat Pump-reversing valve energized for cooling	HC0116	HC0023 HC0042	(2)#SR0225 Relays Same as Above

*Insert SR0157 relay into fourth base of HC0115

LOCATING THE SOLARON CONTROL PANEL

Mount the control panel in a convenient location that allows easy access for electrical wiring and "summer/winter" switch operation. Generally the mechanical room is the best location. Electrical service consisting of one 115 vac circuit is ample to power the 100 VA, 120 VAC/24 VAC transformer accompanying the control panel. Separate power circuits may be needed for the AU0400/AU0500 unit and the auxiliary heating unit (refer to local and national building codes).

Low voltage wiring is needed to connect the Solaron space thermostat to the Solaron control panel as well as between the auxiliary heating unit, damper motors and the control panel. Damper motors are low voltage.

The thermostat MUST be wired through the Solaron control panel, it CANNOT be wired direct to the auxiliary heating unit and Solaron air handling unit.

See instructions with each controller for specific directions and information on wiring schematics.

SOLAR SYSTEMS SENSORS

Sensors must be properly placed in the following locations before system start-up can be accomplished:

1. Tco - Sensor must be in absorber plate air channel (not in duct connection or manifold plenum).
2. Tci - Locate at junction of house return air duct and duct connecting to bottom of heat storage (for systems with by-pass of heat storage for summer water pre-heating, locate in duct to collector where by-pass tees in).
3. Ts - Top of rock in heat bin.
4. Tw - Locate in bottom of water storage tank (not the auxiliary water heater) near inlet of heat exchanger coil. (If using an unwired electric water heater for a storage tank, the thermostat in the tank can be used as Tw. Disconnect power leads from thermostat and power element and wire through terminals that "open" on temperature rise).

SYSTEM START-UP

Please review all steps before proceeding with the system start up of the Solaron Air Handler AU0400/AU0500.

1. Check for proper mounting of belt-drive motor (field installed).
2. Check belt tension.
3. Check pulleys for tightness on shafts.
4. Remove all tools, materials, etc. from inside unit.
5. Check auxiliary heating unit as per manufacturers recommendations.
6. Turn on power to solar air handling unit and controller.
7. Check rotation of solar air handler blower.
8. Turn on power to auxiliary heating unit.
9. Secure all access doors.
10. Check operation of all components and systems as per Solaron control instructions.
11. Give the system owner instructions on how to operate their new Solaron solar system.

BLOWER MOTOR AND DRIVE ASSEMBLY SELECTION PROCEDURE

1. Refer to building plans for air flow and static pressure requirements. Include pressure drop of all dampers and coils in system. (See Selection Example this Manual Pg. 10.)
2. Refer to the Air Delivery Table for each respective air handler:
 - a. select the row which indicates that static pressure required, and
 - b. select the column which shows the CFM required.The point where the row and column intersect will indicate what blower RPM and H.P. motor are needed to deliver the required air flow.

AU0400 AIR DELIVERY TABLE

"W.C." Ext. Static Pressure	CFM												RPM
	1/4 H.P.					1/3 H.P.				1/2 H.P.		3/4 HP	
	300	400	500	600	700	800	900	1000	1100	1200	1300	1400	
.6	-	-	-	-	-	-	-	-	-	1055	1120	1150	
.8	1033	1041	1045	1045	1048	1058	1060	1092	1120	1156	1187	1235	
1.0	1185	1190	1197	1158	1158	1159	1160	1190	1220	1255	1280	1310	
1.2	1300	1300	1295	1279	1265	1260	1270	1290	1310	1335	1360	1389	
1.4	-	1422	1405	1385	1375	1370	1370	1375	1400	1420	1455	-	

AU0500 AIR DELIVERY TABLE

"W.C" Ext. Static Pressure	CFM															RPM
	3/4 H.P.							1 H.P.				1-1/2 H.P.				
	1200	1300	1400	1500	1600	1700	1800	1900	2000	2100	2200	2300	2400	2500	2600	
.8	-	-	-	-	-	-	1000	1021	1040	1064	1088	1116	1143	1171	1200	✓
1.0	1028	1032	1041	1043	1053	1064	1078	1093	1111	1132	1155	1181	1205	1234	1266	
1.2	1121	1122	1124	1127	1135	1143	1154	1167	1182	1200	1223	1248	1274	1307		
1.4	1213	1212	1211	1213	1213	1220	1229	1240	1256	1273	1295	1318	1343			
1.6	1301	1295	1290	1280	1288	1292	1304	1313	1329	1345	1366	1388				
1.8	1383	1376	1367	1363	1363	1365	1376	1387	1400	1417						

DRIVE ASSEMBLY SELECTION

Since the RPM is now known, merely refer to the Drive Assembly Table. Select the RPM needed in the left-hand column. To the right of the RPM column are other columns indicating the number of turns open a specific driver pulley must be in order to deliver that particular RPM. Select whichever column gives the RPM desired. The driven pulley, or fixed blower pulley, is selected from the extreme right hand column. V-belts are noted under each "Driver" column. To determine bore sizes of driver pulleys refer to the Blower Motor Chart for shaft dimensions. Bore size for all fixed pulleys is 3/4" for the AU0400 and 1" for the AU0500.

AU0400 DRIVE ASSEMBLY TABLE

RPM	Browning VL-44 Driver 1/2" or 5/8" Bore	Browning VM50-Driver 1/2" or 5/8" Bore	Fixed Blower Pulley-Driven (Browning AK56) 3/4" Bore
1025	3 1/2 Turns Open	- Turns Open	All RPM Ranges
1058	3	-	"
1092	2 1/2	-	"
1125	2	5	"
1157	1 1/2	4 1/2	"
1190	1	4	"
1224	1/2	3 1/2	"
1257	0	3	"
1290	-	2 1/2	"
1323	-	2	"
1356	-	1 1/2	"
1389	-	1	"
1422	-	1/2	"
1455	-	0	"
V-Belt	4L350	4L360	

RECOMMENDED SELECTION
AREA IS NOT SHADED

AU0500 DRIVE ASSEMBLY TABLE

FAN RPM	Driver - Motor Sheave Browning VP50 (or VM50) X 5/8" (use w/3/4 or 1 H.P. motors)	Belt	Driver - Motor Sheave Browning VP56 X 5/8" (use w/1 or 1 1/2 H.P. motors)	Belt	Driven - Fan Sheave Browning BK70
994	6 Turns Open	A	- Turns Open		All RPM Ranges
1021	5 1/2	A	-		"
1048	5	B	-		"
1075	4 1/2	B	-		"
1102	4	B	-		"
1129	3 1/2	B	-		"
1155	3	B	6	B	"
1182	2 1/2	B	5 1/2	B	"
1209	2	B	5	C	"
1236	1 1/2	C	4 1/2	C	"
1262	1	C	4	C	"
1288	-		3 1/2	C	"
1315	-		3	C	"
1341	-		2 1/2	C	"
1368	-		2	C	"
1395	-		1 1/2	D	"
1421	-		1	D	"

V-BELTS FOR AU0500			
V-Belts	A	5L420	Type V-Belts
	B	5L430	Type V-Belts
	C	5L440	Type V-Belts
	D	5L450	Type V-Belts

AU0400 AND AU0500 BLOWER MOTORS

H.P.	Serv. Factor*	NEMA Frame	Shaft Dia. & Len.	F.L.A. 115V	G.E. Model	Shpg. Wt.
Split Phase Motors - 1725 RPM 115/230V - 60 HZ - 1Ø (Class A)						
1/4	1.35	48Z	1/2" X 2 1/4"	5.2	5KH33FN15T**	15 lbs.
1/3	1.35	56Z	1/2" X 2 1/4"	6.0	5KH35JN30T**	18 lbs.
1/2	1.25	56Z	1/2" X 2 1/4"	9.0	5KH36MN22T**	23 lbs.
Capacitor -Start Motors - 1725 RPM 115/230 - 60 HZ - 1Ø (Class B)						
3/4	1.25	56Z	5/8" X 2 1/4"	11.6	5KC39UN7T**	30 lbs.
1	1.25	56Z	5/8" X 2 1/4"	14.6	5KC48TG726T**	35 lbs.
1-1/2	1.15	56	5/8" X 1-7/16"	21.0	6K324	39 lbs.

The above General Electric "Serv-S-Line" or Dayton motors are 1725 RPM, 115/230 Volt, 60 HZ, 1 phase, automatic reset, thermally protected types recognized by UL under the Motor Component Recognition Program. These motors are open, drip-proof type motors with Class "A" or "B" insulation, ball bearings, resilient base. The motor rotation can be reversed by reconnecting various electrical leads within the motor.

* Motors operated on 200 volts, 60 HZ will have a 1.0 service factor.


** Manufacturers producing motors of equal specification may be used. CLASS B MOTORS ARE RECOMMENDED FOR REPLACEMENT.

Selection Example:

Given: 312 ft² solar collector area (i.e. 2 high, 8 wide, vertical)

Solution: Air handler flow rate (2 CFM/ft²)(312 = 624 CFM, round up to 625 CFM)

The air handler motor and drive assembly must be selected to handle the external static pressure on the Solaron air handler. This selection should be based on the mode which has the highest static pressure drop. The possible modes are:



The highest pressure drop for this example is #1, heating from collectors. The external static pressure drop for this is:

Return grille (see mfg. data)	0.05" w.g.
Return air filter (sized @ 300 to 350 FPM) (see mfg. data)	0.25
Backdraft dampers (2 each) (see A&E Manual pg. 89)	0.20
Collectors (2 panels in series, 2 CFM/ft ²) (see A&E Manual, pg. 80)	0.23
Domestic water coil (see this Manual, pg. 11)	0.08
*Ductwork (see below)	0.19
External Static Pressure	<u>1.00" w.g.</u>

Motor: 625 CFM and 1.0" external static pressure
RPM would be 1158 (see AU0400 Air Delivery Table)
This falls in the region for the 1/2 H.P. motor.

Drive Assembly: 1158 RPM is required at the 700 CFM point. Select 1157 RPM for the 625 CFM requirement. This RPM would be obtained with the driver: Browning VL-44 set at 1-1/2 turns open.

Blower Pulley: Would be Browning AK-56.

Summary: 625 CFM at 1.0" external static pressure
1/2 H.P. motor Solaron #MT0050
Driver VL-44 Solaron #DR0120)
Pulley AK-56 Solaron #DR0120) Package
V-Belt 4 L 350 Solaron #DR0120)

*Ductwork: Static pressure drop through the ductwork is determined by the length and number of fittings. Solaron recommends that ductwork be sized at 0.08" w.g. pressure drop per 100 ft of duct. Fittings and elbows can be estimated by using 15 ft equivalent length of duct for each elbow with turning vanes.

The example above was based on:

(10 elbows)(15' elbow)	=	150'
Length of ductwork	=	90'
Total equivalent length	=	240'

(240 ft)($\frac{0.08"}{100 \text{ ft}}$) = 0.192 w.g. pressure drop
in ductwork

DOMESTIC WATER COIL CAPACITIES

The Solaron domestic water coil is a 1-row copper tube coil.

Calculated coil capacities for size and CFM as listed: 1/2" tube, 10 FPI, one 1/2" inlet and one 1/2" outlet, aluminum fin stock .0055, copper tube .017", capacities based on 3 GPM, ENT. water 50°, E.A.T. 180° F.

AIR HANDLER	SIZE	CFM	FACE VELOCITY	WATER P.D. FT. @ 3 GPM	LV.W.	LV.A	BTU/HR.
AU0400	13 3/4 X 14	600	447	8.20	64.7	146.3	22,050
		800	597	8.20	67.0	150.7	25,500
		1000	746	8.20	69.1	153.7	28,650
AU0500	17 1/2 X 18	1400	642	13.40	80.7	151.7	46,050
		1700	780	13.40	83.9	152.6	50,700

NOTE: MINIMUM WATER FLOW IS 1.5 GPM

The Solaron domestic water heating option is designed to be used with pump #WP3060 (115/60/-Ø ---- .85 amp).

AU0400 - OPTIONAL DOMESTIC WATER HEATING COIL - PRESSURE DROP												
CFM	300	400	500	600	700	800	900	1000	1100	1200	1300	1400
Pres. Drop	.02	.03	.04	.05	.06	.08	.09	.11	.14	.17	.21	.25

Au0500 -											
CFM	1200	1500	1700	1900	2100	2300	2500				
Pres. Drop	.08	.09	.11	.14	.17	.25	.33				

GENERAL OPERATING PROCEDURE
FOR THE SYSTEM OWNER

SOLARON AU0400 AND AU0500 AIR HANDLERS

By simply adjusting the wall mounted thermostat you will be able to maintain a comfortably living or working environment.

By setting the switches located directly under the thermostat, and the sliding levers on top, you can select the type of operation you desire.

For winter heating set the top lever at the desired temperature that you wish to maintain. The thermostat will automatically operate the solar portion of your heating system as well as the auxiliary heating unit if conditions warrant its operation. Please do not "jiggle" the levers.

Should your space conditioning system feature cooling as well as heating, you merely move the switch underneath the thermostat to any desired position ("System Switch - Off - Heat - Auto - Cool). Locating the switch in the "Auto" position will permit the thermostat to automatically place the system in a heating or cooling mode of operation without further adjustment.

Space conditioning systems incorporating a heat pump heating and cooling auxiliary unit will have a thermostat switch position marked "Emerg. Heat". The only function of this switch is to provide emergency electric heat should the heat pump malfunction during a period of time when a serviceman is not readily available.

Nominal maintenance is required with this system. Please refer to "Maintenance Instructions" provided in the Installation Manual.

Please call your qualified Soloron serviceman should problems develop.

Installing Soloron Solar System Contractor

Name: _____

Address: _____

Phone: _____

The Soloron controller requires that its "Summer-Winter" switch be placed in the appropriate season position. When switching seasons it may be necessary to move some system dampers. Please have your installing contractor indicate these dampers to you.

Maintenance Instruction

The AU0400 and AU0500 require minimal upkeep for economical and long lasting operation.

Blower Type 1 - Permanently sealed bearings - no oil required.

Motor Type 2 - Blower Motor - Oil twice a year (#20 S.A.E. non-detergent oil).

Blower bearings - Permanently sealed - no oiling required.

V-Belt - Check wear and tension, replace if necessary.

Damper Motors - Oil with #10 S.A.E. non-detergent oil (similar to #465 Anderol or Goodlight #10 oil.) Twice a year.

Water Pump - The Grundfos circulator pump requires no oiling as it is water lubricated during normal operation.

HEAT STORAGE UNIT

INSTALLATION

MANUAL


PRECEDING PAGE BLANK NOT FILMED

COMMERCIAL HEAT STORAGE UNIT

STORAGE CAPACITY GREATER
THAN 270 CU. FEET

SOLARON[®] INSTALLATION CORPORATION Solar Energy Systems **MANUAL**

300 GALLERIA TOWER, 720 S. COLORADO BLVD
DENVER, COLORADO 80222



ORIGINAL PAGE IS
OF POOR QUALITY

LT 3018



Copyright

May 1978
50

Solaron Corporation



THIS MANUAL IS INTENDED TO BE USED ON
PROJECTS WITH A MINIMUM COLLECTOR AREA
OF 540 SQUARE FEET.

TO THE READER:

THIS MANUAL IS INTENDED TO BE A GENERAL GUIDE FOR SIZING
AND BUILDING THE HEAT STORAGE UNIT FOR A SOLARON SOLAR
HEATING SYSTEM. THE STORAGE UNIT FOR SPECIFIC PROJECTS
SHOULD BE CHECKED TO ENSURE IT IS DESIGNED AND BUILT
PROPERLY TO ACCOUNT FOR ALL THE VARIABLES INVOLVED.

The drawings, illustrations and text contained in this manual are
protected by copyright. Publication, reproduction, or use of all
or any part of this manual (except for actual construction and de-
sign use with Solaron systems engineering plans) without special
written permission from Solaron Corporation, is prohibited.

Due to our policy of continual improvement to our products, Solaron
reserves the right to change the materials, installation procedures
and specifications without notice.

Solaron assumes no responsibility for improperly designed or con-
structed heat storage units where this manual is used as a guide.

KKBNA

KETCHUM • KIMMEL • GARRETT • NICKEL • AUSTIN, INC. • CONSULTING ENGINEERS

June 1, 1978

Solaron Corporation
300 Galleria Tower
720 S. Colorado Blvd.
Denver, Colorado 80222

Re: Solaron Installation Manual
Commercial Heat Storage Unit


Gentlemen:

Structural details and specifications contained in this manual are derived from engineering analysis and design calculations done by KKBNA, Consulting Engineers. These calculations are based on strength of materials and performance criteria in accordance with latest design standards and specifications.

The structural drawings, material and installation specifications in this manual have been reviewed to check their conformance to the design calculations.

Sincerely,

KKBNA, Inc.


Charles D. Keyes
Vice President

CDK:et



ORIGINAL PAGE IS
OF POOR QUALITY

TABLE OF CONTENTS

	<u>PAGES</u>
DESCRIPTION	54
GENERAL NOTES	55
HEAT STORAGE UNIT AND ROCK SIZING	57
HEAT STORAGE UNIT - CONCRETE CONSTRUCTION	59
HEAT STORAGE UNIT - WOOD CONSTRUCTION	61
HEAT STORAGE UNIT - ATTACHMENT DETAILS	64
OPTIONAL AIR HANDLER AND DUCT LOCATIONS	65
METAL LATH SAMPLE	66
BOND BEAM BLOCK AND TRANSITE DUCT DETAILS	67
ROCK AND SIZING METHOD	68
HEAT STORAGE UNIT CONSTRUCTION CHECKLIST	69

DESCRIPTION

The use of pebbles in the heat storage unit is particularly effective with an air circulating solar heating system. The pebble bed maintains a high degree of temperature stratification (i.e., hot on top and cold on the bottom). This allows air to be provided at the highest available temperature to the heated space from the top of the pebble bed. It also allows air to return from the bottom of the bed to the collector at essentially room temperature, thus maximizing efficiency of solar heat collection and delivery.

The heat storage container can be constructed of any of the following materials:

- a. Poured, reinforced concrete with a rigid fiberglass insulation inner liner (i.e., insulation is inside, separating the rock from the concrete wall).
- b. Wood frame, plywood on 2 x 4 or 2 x 6 studs with a non-combustible inner liner suitable for temperatures as high as 200°F.

The heat storage unit should be built and installed by the local contractor to Solaron standard drawings and specifications. The air flow through the pebble bed must be vertical. Horizontal flow in pebble beds must be avoided due to channeling and "hot spot" problems.

It is important that the heat storage container be airtight and insulated as follows:

- a. Storage unit inside a heated space: R-11 minimum.
- b. Storage unit inside an unheated space: R-30 minimum.
- c. Storage unit inside a heated space with wall in unheated area: R-30 minimum.

The heat storage unit can be conveniently placed in the basement or crawl space or set into the ground. Buried heat storage units must be waterproofed on all buried external surfaces (do not use asphalt or other sealers on inside walls) DO NOT bury heat storage unit below the high ground-water level due to possibility of water leakage into heat storage unit and resulting loss of performance. Support footings must be designed for local soil conditions. Due to the weight of the rocks, it should not be placed in the attic or on the upper floors without proper structural support. Typical floor loading with a rock depth of 5 feet is 500 pounds per square foot of floor area.

Design Criteria

- Rock:
- Hard dense rock (i.e., density = 100 lbs./ft.³, or greater).
 - River gravel or hard, dense crushed rock is OK.
 - Uniform size (i.e., most systems will use rock sized at 3/4" to 1-1/2" in diameter).
 - Clean the rock before it is loaded in the storage box (i.e., wash it).
 - Minimum of fines (i.e., 0 to 5%).
- Storage:
- Airtight, insulated, structurally sound and, if buried, externally waterproofed. The inside surface materials must be able to withstand temperatures of approximately 200°F.



GENERAL NOTES

1. ANY SUBSTITUTION OF MATERIALS, CHANGES OF DIMENSIONS OR OTHER CHANGES IN HEAT STORAGE UNIT AS SHOWN MUST BE APPROVED BY SOLARON CORPORATION IN WRITING PRIOR TO START OF CONSTRUCTION.
2. ALL FOOTING AND STRUCTURAL SUPPORTS ARE THE RESPONSIBILITY OF OWNER AND/OR ARCHITECT AND SHALL BE SIZED ACCORDING TO SOIL REPORT INFORMATION. COORDINATE THIS DRAWING WITH ARCHITECTURAL DRAWINGS FOR TYPE, SIZE AND LOCATION OF FOOTING AND STRUCTURAL SUPPORTS.
3. JOINTS, CRACKS, SEAMS AND PENETRATIONS INSIDE AND OUT IN WALLS, FLOOR AND LID OF HEAT STORAGE UNIT SHALL BE SEALED AIR-TIGHT WITH DOW CORNING #732 SILICONE SEALANT CAULK OR APPROVED EQUAL.
4. BOND BEAM BLOCK - 2 OR 3 WEB. WEBS MUST BE AT A RIGHT ANGLE TO WALL CONTAINING BOTTOM OPENING (SEE DETAIL FOR TRANSITE DUCT AND BOND BEAM BLOCK ORIENTATION).
5. METAL LATH - USE JR. DIAMOND MESH 3.4 LB./SQ. YD. (GALVANIZED) ADJOINING PIECES TO BE OVERLAPPED A MINIMUM OF 6". TURN EDGE UP ONTO INNER WALLS OF HEAT STORAGE UNIT A MINIMUM OF 12".
6. THE ROCK SHALL BE ROUND WASHED RIVER ROCK OR STONE. 95% OF THE ROCK SHALL BE THE SIZE SHOWN ON THE PLANS WITH A MINIMUM AMOUNT OF FINES (I.E., LESS THAN 1/4" DIAMETER). THE ROCK SHALL BE CLEAN AND FREE OF DIRT. NORMALLY THE ROCK IS SIZED BY SCREENING (THAT ROCK WHICH PASSES THROUGH A 1-1/2" SCREEN BUT NOT A 3/4" SCREEN IS THE NORMAL SIZE).
7. TREATMENT FOR THE INSIDE SURFACES OF THE BOX SHALL BE SUITABLE FOR TEMPERATURES OF 200°F. NO COMBUSTIBLE MATERIAL WILL BE USED.
8. NON-LOAD BEARING LID SHALL BE CONSTRUCTED OF 1/2" EXTERIOR GRADE PLYWOOD INSIDE AND OUT--2 x 4'S - 24" ON CENTER AND 1/2" MOISTURE-RESISTANT TYPE "X" DRYWALL ON INSIDE SURFACE TOWARD PEBBLES. 28-GAUGE SHEET METAL CAN BE USED IN LIEU OF DRYWALL.
9. LOAD BEARING LID SHALL BE CONSTRUCTED OF 1/2" EXTERIOR GRADE PLYWOOD INSIDE AND OUT--2 x 6'S - 24" ON CENTER AND 1/2" MOISTURE-RESISTANT TYPE "X" DRYWALL ON INSIDE SURFACE TOWARD PEBBLES. 28-GAUGE SHEET METAL CAN BE USED IN LIEU OF DRYWALL.

HEAT STORAGE UNIT DESIGN PARAMETERS		
DESIGN TEMPERATURE TOP AND BOTTOM	PRESSURES	AIR FLOW
MAXIMUM TEMPERATURE (200°F)	ENTIRE STORAGE UNIT	THRU ROCK 20 TO 40 FPM
OPERATING RANGE (90° TO 180°)	ATMOSPHERIC PRESSURE ±3" W. C.	THRU OPENINGS 800 TO 1000 FPM
MINIMUM TEMPERATURE (AMBIENT)		

GENERAL NOTES

(continued)

9. CONCRETE:

- A. ALL CONCRETE SHALL ATTAIN 3,000 PSI ULTIMATE COMPRESSIVE STRENGTH IN 28 DAYS.
- B. ALL REINFORCING SHALL BE HIGH STRENGTH DEFORMED BARS ASTM DESIGNATION A615, GRADE 40 OR GRADE 60.

10. STEEL:

ALL STRUCTURAL STEEL SHALL CONFORM TO ASTM SPECIFICATION A36.

11. MASONRY:

- A. ALL MORTAR SHALL DEVELOP 1,800 PSI ULTIMATE COMPRESSIVE STRENGTH IN 28 DAYS.
- B. ALL MASONRY SHALL DEVELOP 1,500 PSI ULTIMATE COMPRESSIVE STRENGTH IN 28 DAYS.
- C. ALL REINFORCING SHALL CONFORM TO ASTM 615, GRADE 40 OR GRADE 60.

12. WOOD:

- A. ALL FRAMING LUMBER SHALL BE DRY HEM-FIR GRADE 2.
- B. ALL PLYWOOD SHALL BE OF THICKNESS SPECIFIED C-C EXT DFPA OR BETTER. NAILED TO SUPPORTS WITH 10d NAILS SPACED 6" O.C. AT PANEL EDGES AND SPACED 12" O.C. AT ALL OTHER SUPPORTS. PLYWOOD SHALL BE APPLIED WITH FACE GRAIN PERPENDICULAR TO SUPPORTS.

13. TRANSITE DUCT:

TRANSITE DUCT CAN BE USED INSTEAD OF THE EXTERNAL BOTTOM DUCT OPENING TO ALLOW AIR FLOW TO AND FROM THE BOTTOM OF THE HEAT STORAGE UNIT WITHOUT PENETRATING THE UNIT OR RUNNING AN EXTERNAL DUCT. EXAMPLE: WHEN MECHANICAL EQUIPMENT IS INSTALLED ON TOP OF THE HEAT STORAGE UNIT OR WHEN THE HEAT STORAGE UNIT IS BURIED.

ONE 16" DIAMETER DUCT SERVES 270 CU. FT. OF STORAGE AT 1,080 CFM.
TWO 16" DIAMETER DUCTS SERVE 540 CU. FT. OF STORAGE AT 2,160 CFM.
THREE 16" DIAMETER DUCTS SERVE 810 CU. FT. OF STORAGE AT 3,240 CFM.



Copyright

May 1978

Solaron Corporation

HEAT STORAGE UNIT AND ROCK SIZING SHEET

- a. VOLUME: Storage size is determined from the collector area. 1/2" ft.³ to 3/4" ft.³ of rock is required per ft.² of collector area.

Collector Area = _____ ft.²

Volume = (_____ ft.³/ft.²)(_____ ft.² collector) = ft.³

(_____ ft.³)(100 lbs./ft.³)(1 ton/2,000 lbs.) = tons

(_____ ft.³) : 27 ft.³/cu. yd. = cu. yds.

- b. DIMENSIONS:

(_____ ft.³) : (_____ * ft. rock depth) = ft.² floor area

Storage unit inside dimensions = _____ ft. long x _____ ft. wide

Minimum dimension of 3' for length or width

- c. ROCK SIZE: (see chart below)

(_____ cfm) : (_____ ft.² floor area) = fpm

_____ fpm } = 3/4" to 1-1/2" and _____ " w.g.
_____ ft. rock depth } Ø rock static pressure drop thru rock

- d. AIR INLET/OUTLET SIZES: Size duct connections at 800 to 1,000 fpm

Top: _____ " high x _____ " wide

Bottom: _____ 8 " high x _____ " wide

(NOTE: Bottom opening must always be at least twice as wide as top opening to account for restriction caused by bond beam block. Optional top opening as per pages 6 and 13.)

The following data should be used to determine the proper combinations of rock size and rock depth. Minimum allow. static pressure loss 0.12" w.g.

STATIC PRESSURE LOSS THRU PEBBLE BED STORAGE UNIT (INCHES W.G.)				
FACE VELOCITY ACROSS ROCK BOX →		20 FPM	25 FPM	30 FPM
ROCK DEPTH-FEET	ROCK SIZE			
5'	3/4" to 1-1/2"	0.12"	0.22"	0.31"
6'	3/4" to 1-1/2"	0.14"	0.23"	0.34"
7'	3/4" to 1-1/2"	0.17"	0.27"	0.40"


* 5'0" minimum depth for commercial unit; 7'0" maximum rock depth.

© Copyright May 1978 Solaron Corporation

HEAT STORAGE UNIT SIZING

ALTERNATE OPENING LOCATIONS

(note that top & bottom openings need NOT be located on same side)



TONS OF ROCK
(100 lbs. per CU. FT.)

CU. FT. ROCK
(A x B x N)

ORIENTATION

DIMENSIONS					
A		F		K	
B		G		L	8°
C		H		M	
D		I		N	
E		J			

ORIGINAL PAGE IS
OF POOR QUALITY

NOTE: 14" x 14" high sidewall opening location can be used when air handler outlet is mounted directly to box.

©

Copyright

May 1978

Solaron Corporation

COMMERCIAL HEAT STORAGE UNIT

CONCRETE CONSTRUCTION

1. WALL CONSTRUCTION TO BE 8" MINIMUM REINFORCED CONCRETE.


VERTICAL AND HORIZONTAL RE-BAR:

- A. 4 - #5 RE-BAR CONTINUOUS 2 EACH FACE.
- B. #4 RE-BAR AT 8" O.C. VERTICAL IN OUTSIDE FACE.
- C. #5 RE-BAR AT 8" O.C. HORIZONTALLY FOR 8" THICK WALLS.
- D. DOWEL WALL TO FLOOR WITH ONE OF THE FOLLOWING:
 1. #4 RE-BAR "L" 1'-6" x 1'-6" AT 16" O.C.
OR
 2. 5/8" \varnothing x 8" HEADED ANCHOR BOLT W/NUT AT 18" O.C.
OR
 3. 5/8" \varnothing EXPANSION ANCHOR W/5" BOLT AT 24" O.C.

CENTER ANY OF THE OPTIONS ON WALL.

2. FORM OUT FOR BOTTOM AND TOP OPENINGS AS REQUIRED FOR A GIVEN APPLICATION WITH 2 X DIMENSION LUMBER WHICH SHOULD BE LEFT INTACT WHEN FORMS ARE REMOVED TO PROVIDE MOUNTING FRAME FOR DUCTWORK. PLACE TWO #5 RE-BARS (1 ON EACH FACE) WITH 2'-0" PROJECTION AROUND ALL OPENINGS IN CONCRETE. PROTECT WOOD FRAMING FROM AIRSTREAM WITH SHEET METAL COLLAR OR GYP BOARD. THE FINISHED FRAMED INSIDE DIMENSION SHOULD BE THE SAME SIZE AS THE DUCT. SEE EXAMPLE BELOW:

EXAMPLE: FOR AN 8" x 20" DUCT, THE OPENING SHOULD BE



3. INSULATE INTERIOR SURFACE WITH 2" RIGID FIBERGLASS BOARD INSULATION (6 LB. DENSITY WITH R-8 MINIMUM), "CERTAIN-TEED #1B600, 2" PLAIN. SECURE TO WALL. DO NOT USE STYROFOAM OR URETHANE INSULATION.
5. INSTALLATION SHALL COMPLY WITH ALL APPLICABLE NATIONAL AND LOCAL BUILDING CODES.



Copyright


May 1978

Solaron Corporation

COMMERCIAL HEAT STORAGE UNIT CONCRETE

NOTE:

IF AIR HANDLER LOCATION OPTION NO. 1
IS USED A 14"x14" OR 18"x18" OPENING WITH
ROCKS SCOOPED AWAY SHALL BE NEEDED
SEE pg. 12



NOTE: INSULATION R-11 MIN. (R-30 IN UNHEATED AREA)

COMMERCIAL HEAT STORAGE UNIT


WOOD CONSTRUCTION

1. WALL CONSTRUCTION TO BE SINGLE 2" x 8" NAILED VERTICALLY 16" O.C. (NO TOE NAILING). VERTICAL 2" x 8" AT CORNER TO BE NAILED. A SINGLE 2" x 8" HORIZONTAL BEAM WILL BE NAILED IN (USING 'SIMPSON' LU 26 JOIST HANGER AT EACH VERTICAL STUD) 6'-0" FROM FLOOR ALL AROUND. A DOUBLE 2" x 8" BEAM HORIZONTAL AT TOP AND BOTTOM TO BE NAILED IN (USING 'SIMPSON' LU 26 JOIST HANGER AT EACH VERTICAL STUD). THE INLET AND OUTLET OPENING TO BE FRAMED WITH 2" x 8" BLOCKING; OUTSIDE DRYWALL SHEATHING TO BE INSTALLED AFTER WALL FRAMING IS SET, ANCHORED AND INSULATED. INSIDE SHEATHING TO BE 1/2" EXTERIOR GRADE PLYWOOD OVERLAID WITH 1/2" TYPE X DRYWALL (ALL SEAMS TO BE CAULKED WITH DOW CORNING 732 SILICONE SEALANT. 28-GA. SHEET METAL MAY BE SUBSTITUTED FOR THE DRYWALL. ROCK BOX MUST BE AIRTIGHT; SEAL ALL JOINTS.
2. INSULATE ALL VOIDS WITH 3" TO 3-1/2" FIBERGLASS BATT INSULATING (R-11 MINIMUM). ADDITIONAL INSULATION REQUIRED WHEN PEBBLE BED IS LOCATED IN AN UNHEATED SPACE (R-30 MINIMUM). DO NOT USE STYROFOAM OR URETHANE INSULATION AS BED INNER LINER.
3. TIE RODS RUNNING IN EACH DIRECTION HORIZONTALLY FROM FLOOR (6'-0") THROUGH WALL SHALL BE STEEL TIE RODS 7/8" DIA. THERE SHALL BE TWO 5" x 6.7# CHANNEL STEEL BEAMS ON TOP AND BOTTOM OF TIE ROD WHERE THE ROD PENETRATES OUTSIDE OF WALL. AT POINT OF TIE ROD CONTACT WITH CHANNEL STEEL BEAMS SHALL BE A 3/8" x 3" x 3" STEEL PLATE WELDED TO THE TWO CHANNEL BEAMS WITH A BOLT AND NUT AT EACH END OF TIE RODS. PRE-TENSION RODS UNTIL WALL CENTERS HAVE CONCAVED INWARD APPROXIMATELY 1/8" BEFORE APPLYING SEALANT TO JOINTS.
4. INSTALLATION SHALL COMPLY WITH ALL APPLICABLE NATIONAL AND LOCAL BUILDING CODES.

COMMERCIAL HEAT STORAGE UNIT WOOD

NOTE:

IF AIR HANDLER LOCATION OPTION NO. 1
IS USED A 14"x14" OR 16"x16" OPENING WITH
ROCKS SCOOPED AWAY SHALL BE NEEDED
SEE pg. 12



NOTE: INSULATION R-11 MIN. (R-30 IN UNHEATED AREA)

NOTE: INTERIOR SURFACES AND INSULATION OF ROCK BOX MUST BE
NON-COMBUSTIBLE AND SUITABLE FOR TEMPERATURES UP TO 200° F.



Copyright


May 1978

Solaron Corporation






COMMERCIAL HEAT STORAGE UNIT WOOD

NOTE:

ALL SURFACES IN CONTACT
WITH AIR STREAM MUST BE
COVERED WITH NON-COMBUSTIBLE
MATERIAL (STEEL METAL OR
GYP. BOARD)



COMMERCIAL HEAT STORAGE UNIT ATTACHMENT DETAILS





© Copyright May 1978

Solaron Corporation

OPTIONAL AIR HANDLER & DUCT LOCATIONS

NOTE: FOR USAGE SEE
GENERAL NOTE 13, pg. 3.



(C)


Copyright

May 1978




Solaron Corporation

METAL LATH SAMPLE


(MUST BE GALVANIZED)




BOND BEAM BLOCK & TRANSITE DUCT DETAILS



TOP



SIDE



ISOMETRIC


TRANSITE DUCT DEFLECTOR - SUPPORT BASE

ROCK & SIZING METHOD

ANY ROCK USED IN THE HEAT STORAGE UNIT MUST BE CLEAN AND CONTAIN LESS THAN 5% FINES. ROUND RIVER BED ROCK OF A GRANITE TYPE IS PREFERRED. HOWEVER, FRACTURED HARD ROCK MAY BE USED.

WASH ALL ROCK BEFORE IT IS INSTALLED IN THE HEAT STORAGE UNIT. WASHING MAY TAKE PLACE AT THE QUARRY OR AT THE JOB SITE. ROCK MAY BE POURED INTO PLACE WHILE IT IS DAMP BUT SHOULD NOT BE DRIPPING WATER. UNDER NO CIRCUMSTANCES SHOULD ROCK BE WASHED AFTER IT IS IN PLACE.

ROCK SIZING METHOD



HEAT STORAGE UNIT CONSTRUCTION CHECK LIST

	<u>Refer to</u>
<input type="checkbox"/> Calculate size of heat storage unit	57
<input type="checkbox"/> Determine location of storage unit	54
<input type="checkbox"/> Excavate (if required)	54
<input type="checkbox"/> Prepare and install footings	55
<input type="checkbox"/> Construct walls of storage unit	59-65
<input type="checkbox"/> Install tie rod thru walls of storage unit	60-65
<input type="checkbox"/> Seal interior of storage unit airtight	55
<input type="checkbox"/> Install wall insulation in concrete box	59, 60
<input type="checkbox"/> Install bond beam block (if required, install transite duct support base and transite duct)	55, 60, 62, 63, 67
<input type="checkbox"/> Install diamond mesh over bond beam block overlap 6" and turn up wall 12". Clamp mesh to transite duct, if used	54, 60, 62, 66, 67
<input type="checkbox"/> Obtain rock of proper size	55, 68
<input type="checkbox"/> Clean rock	55, 68
<input type="checkbox"/> Fill rock carefully onto diamond mesh	59, 61
<input type="checkbox"/> Fill remainder of storage unit, leave supply opening clear and maintain 8" plenum space with smooth surface	59, 61
<input type="checkbox"/> Caulk and install lid to seal airtight	55

SYSTEM OWNER'S MANUAL
FOR
OPERATION AND MAINTENANCE

SYSTEM OWNER'S MANUAL

SPACE HEATING
SPACE HEATING
DOMESTIC WATER PREHEAT



SOLARON®
SOLAR ENERGY SYSTEMS

SOLARON® CORPORATION

SYSTEM OWNER'S MANUAL

You are to be congratulated on what could well be the most gratifying purchase you will ever make in your life. By reading the material contained within this manual you will be able to better understand and appreciate not only your investment, but also your personal contribution to help in easing the Nation's energy crisis.

CONTENTS

PAGE NO.

◦ A Description of your SOLARON® System	74
- Overview of System	74
◦ General System Description.	75
- Collectors	79
- Heat Storage.	80
- Soloron® Air Handling Unit	82
- Gravity-Operated Dampers	82
- Domestic Water Preheater	82
- System Controls	83
- Auxiliary Heating System	83
◦ How to Operate your SOLARON® System	87
◦ Routine Maintenance	89
◦ Steps to Follow to Obtain Maximum Performance from your SOLARON® System.	90
◦ If your SOLARON® System Does Not Work	92

System Installed By:

System Supplied By:

PRECEDING PAGE BLANK NOT FILMED

Soloron® is a registered trade name of the Soloron Corporation.

©Copyright 1978 Soloron Corporation, 720 So. Colorado Blvd.,
Denver, Colorado 80222.

A DESCRIPTION OF YOUR SOLARON® SYSTEM


Overview of System

Space heating with solar energy has been the subject of research and development in the United States since 1938 when MIT built its first solar heated house. In 1943, Dr. G.O.G. Löff built and installed a successful solar air heating system in his home in Boulder, Colorado; a prototype system, also using circulating air, has worked continuously in his Denver home since 1957 with no major problems and minor maintenance cost.

Thus, the technology of space heating by a solar energy air system has been well developed for a number of years and could have been applied to large scale use if it was economical. However, low fossil fuel and electrical energy costs discouraged the use of relatively expensive solar heating systems until the 1973 oil and energy shortages. When fuel and electricity prices began a rapid upward spiral, solar heating became economically competitive in many parts of the world.

In early 1974, Dr. Löff and several associates organized Solaron Corporation to design, manufacture, and market solar heating systems for residential, commercial, and industrial buildings. The company's technical staff designed a solar air heating production model, based on Dr. Löff's knowledge and the accumulated years of practical experience with the 1957 prototype system in the Löff residence. Since 1974, Solaron has furnished solar heating systems for a large number of residences and commercial buildings throughout the U.S.A. and overseas.

The Solaron Corporation solar heating system is effective in residential, commercial and industrial buildings. Air is the circulating heat transfer medium. The patented flat plate collector array consists of a combination of factory preassembled panels which can be mounted directly on a south facing roof of proper tilt, with proper supports on a flat roof or in another suitable location near the space to be heated. A factory pre-assembled air handling unit containing automatically actuated dampers, an optional domestic water preheater and a temperature control panel completes the Solaron package. A full-size, auxiliary conventional heating system and the installation labor are provided by others.



GENERAL SYSTEM DESCRIPTION


This drawing is intended to show a typical installation and relationship of the collectors, air handler, heat storage unit, motorized dampers, back-draft dampers and domestic water coil. The dampers used in solar AIR systems are very important to the successful operation of the system. Therefore, Soloron provides special dampers with airtight seals which are designed for long life and trouble-free service. The purpose or function of each damper is described below:

- MD-1: Motorized damper. Closes to prevent cold air from falling from the collector and leaking into the system in the "Heating from Storage Mode"
- MD-2: Motorized damper. Closes in the "Storing Heat Mode" to direct air to the heat storage unit.
- BD-1: Backdraft damper. Closes in the "Storing Heat Mode" to prevent reverse flow down the return air duct.
- BD-2: Backdraft damper. Closes in the "Heating from Storage Mode" to prevent the possibility of cold air from being drawn down from the collector and leaking into the system.

The following are generalized system modes of operation. The system in your building may have different design features.


Mode A. Heating from Collectors

Air, the circulating heat transfer medium, is drawn through the flat plate collector where it is normally heated to about 120°F - 150°F. When the space requires heat, the solar heated air is drawn through the air handling unit in which a motorized damper is automatically opened to direct the hot air through the auxiliary heating unit and out into the space. The air then returns to the collector at about 70°F where it is again heated and the cycle repeats itself.




Mode B. Storing Heat

When the space temperature is satisfied, the automatic control system diverts the solar heated air into the heat storage unit where the heat is absorbed by the pebble bed. Relatively cool air from the bottom of the heat storage unit (i.e., normally at 70°F) returns to the collector where it is heated.




Mode C. Heating from Storage

At night or on cloudy days when solar energy is unavailable and when heat is needed in the space, the automatic control system directs the building return air into the bottom of the heat storage unit, up through the pebbles where the air is heated, through a portion of the air handling unit and into the space via the auxiliary heating unit fan. When the solar heated air does not maintain the space thermostat setting, the automatic control turns on the auxiliary heater to add the required heat.




Mode D. Summer Water Heating

In the summer, when space heating is not required, air is drawn through the collector where it is heated and then across the water heat exchanger coil. The solar heated air transfers its heat to the water which is being circulated through the coil and the cooled air is then return back to the collector inlet.




Mode E. Heat Pump Systems - Second Stage Heating (solar energy available)

Heat pump systems should not operate in their heating mode when the return air temperature is high (above 75°F). Therefore, on a call for second stage heating with heat pumps, the solar system is bypassed. All the return air goes through the MD-3 bypass damper to the indoor heat pump unit. Note the solar energy is not wasted since it will go into storage and be used later when there is a call for first stage heating.



Mode F. Heat Pump Systems - Second Stage Heating (no solar)

This is the same as Mode E except the solar air handling unit is not storing heat. All the return air goes through MD-3. As soon as there is a call for first stage heating the system will heat from storage and the system operates as in Mode C.




Collectors

The Solaron air heating collector has a flat absorber and heat exchanger plate, is internally manifolded and insulated, is constructed of steel and is covered by special high transmittance glazing. The solar radiation is absorbed and converted to useful heat energy with air as the transfer medium. The collector is subjected to its most severe thermal conditions of up to 400°F when it is in direct sunlight and the system is not operating because there is no heating requirement. The collector performance is optimal if it is oriented due South and tilted at an angle of latitude plus 5 to 15 degrees for space heating and latitude minus 5 degrees for domestic hot water heating and many process heat applications. A variance of 60 degrees from due South, as an example, will generally require an additional 20 percent collector area and a 5 degree variation in tilt from optimum will require approximately 3 percent additional collector area.

The air flow in the Solaron collector passes beneath the absorber in a duct that is formed by the absorber and a second metal sheet. The absorber, therefore, is insulated by a dead air space between it and the glazing. This design makes for a more efficient collector in most applications and protects the absorber surface from dust or other airborne contamination.


The collector utilizes a patented air manifold system to minimize field installation labor and assure uniform high performance. The manifold system replaces most of the ductwork normally used to interconnect other types of air heating collectors.




Heat Storage


The use of pebbles in the heat storage unit is particularly effective with an air circulating solar heating system. The pebble bed maintains a steep temperature stratification (i.e., hot on top and cold on the bottom). This allows air to be provided at the highest available temperature to the heated space from the top of the pebble bed. It also allows air to return from the bottom of the bed to the collector at essentially room temperature. This ensures maximum efficiency of solar heat collection and delivery.

The most efficient and least expensive heat storage device for use with a circulating air system is a bin of clean pebbles between 3/4 inch and 1 1/2 inches in size. The storage volume is normally sized in accordance with the parameters illustrated. Increasing the storage above the range of 0.50 to 0.75 cubic feet for every square foot of collector will have little or no effect on increasing heat obtained from the solar system.




• EFFECT OF ROCK STORAGE MASS





Charge Cycle*

A typical solar system during the winter starts in the morning after having used most of the stored solar energy for the nighttime heating requirement. The collector outlet temperatures (and temperatures into storage) typically peak during the middle of the day and are lower in the early morning and late afternoon. This results in stratified layers of heat such as 120°F to 140°F at the top, approximately 140°F near the middle, 100°F to 120°F near the bottom and 70°F at the bottom.



Discharge Cycle*

Heat is extracted from the storage unit in reverse of the charge cycle.

The energy stored in the late afternoon is used first.

Energy stored at the highest temperatures during the middle of the day is used at night during the peak heating hours.

Energy stored from the early morning hours is used towards the end of the peak nighttime heating hours.


* Propagation of the temperature profile through the pebble bed during a typical charge-discharge cycle as measured in actual system operation at Colorado State University.

The length of time that the system can heat from the solar storage unit will vary as a function of the amount of solar energy available and how cold it is outside. There can be times when there will be no heat in the storage unit (i.e. cold winter days when all of the solar energy collected during the day is entirely used up during the same day).

Solaron Air Handling Units


Solaron provides a standard factory preassembled air handling unit, including a blower and field installed motor. A separate pair of motorized dampers is furnished for mounting in the duct system. The installer attaches ducts from the collector, heat storage, and auxiliary heating system to the air handling unit. Certain systems may require additional motorized dampers.

The air handler can be mounted either vertically or horizontally. The motorized dampers are mounted at convenient positions in the ductwork between the collector and the air handler and between the air handler and the auxiliary heating system.



Gravity-Operated Dampers

A typical Solaron system will contain two gravity-operated dampers located on the return air side of the solar system. These dampers automatically open when air is blown through the ducts by the solar system. However, when the system is not operating these dampers will automatically close to prevent the cold night air from leaking down the ducts and into the heat storage unit.



Domestic Water Preheater

SEE SCHEMATIC ON P.13

This is an option which may or may not be included in your system. The water preheater system contains an air-water heat exchanger coil, a small water circulating pump and an insulated storage tank. During all months of the year, hot air from the collector heats the water circulated by the pump through the heat exchanger coil. Warmed water is collected in the insulated storage tank, from which the regular water heater draws its supply. The preheater is replenished from the cold water line. A simple control turns the pump on when solar heated air is being delivered from the collector. While many systems have two domestic water tanks, certain system designs require only one.

System Controls

As part of the complete heating system, Solaron furnishes an automatic control system, including the necessary sensors and switches. The controller acts to shift the system automatically from one mode of operation to another, as required. The control system turns on the blower for collector operation when the sun is providing enough energy for storage or use. It also controls the blower in the auxiliary heating unit when air circulation to the heated space is required. The controller shifts operation between heating the building space and storing heat during a sunny day, and later acts to circulate heated air through the storage into the building at night. In addition, the control system turns on the auxiliary furnace when more heat is required than the solar collector or heat storage can furnish.



Auxiliary Heating System

Every solar heated building requires a full size, auxiliary heating unit which uses locally available fuel (electricity, gas, oil, wood, propane, etc.). Because Solaron's solar heating systems use air as the circulating heat transfer medium, they are easily integrated into conventional air distribution systems.

The auxiliary unit must be sized to furnish the entire building heating load on the coldest day of the year.

The auxiliary heating is furnished by gas, oil, or electric duct heaters or hydronic coils mounted in the conventional duct system. The automatic damper system in the Solaron air handler will automatically respond by directing air to the space or to storage, as required. Control interlock between the solar system and the conventional heating unit utilizes standard temperature control practices.

The following information sets forth a detailed description of the control logic to operate a Solaron system. You should refer to the following system schematic and the legend to assist in understanding this section.

There are two models of Solaron controllers used in most Solaron systems:

- 1.) For use with conventional heating systems (which may include air conditioning).
- 2.) For use with most conventional heat pump auxiliary systems.

I. SOLAR ENERGY AVAILABLE. When a 40°F differential is achieved between sensors T_{co} (collector outlet) and T_{ci} (collector inlet), the following events take place:

A. Storing Heat - no demand for space heating.

1. Differential thermostat in controller will energize control circuit to: open MD-1; turn on Solaron air handler blower; turn on hot water pump (optional); close MD-2.

B. First Stage Heating - demand for solar heat in space.


1. The controller circuit will: turn on auxiliary unit fan (auxiliary heat source is off); open MD-2.

C. Second Stage Heating - demand for additional heat (auxiliary).

1. The conventional space heating control circuit will bring on the auxiliary heat source (gas, electric, oil, etc.).
2. The heat pump control circuit will bring on the heat pump compressor and fully open MD-3. (Note: MD-2 closes on second stage for heat pump.)

D. Third Stage Heating (heat pump applications only).

1. A second thermostat will bring on electric resistance strip heating elements in auxiliary heating unit. (An outdoor temperature sensor may be used instead of a second thermostat.)



SYSTEM SCHEMATIC

Sequence of Operation									
MODE	MD-1	MD-2	BD-1	BD-2	D-1	D-2	AHU	AUX FAN	MD-3
Heating from Collector	O	O	O	O	O	C	On	On	⊗
Heating from Storage	C	O	O	C	O	C	Off	On	⊗
Storing Heat	O	C	C	O	O	C	On	Off	⊗
Water Heating (Summer)	O	C	C	C	C	O	On	Off	⊗
Air Conditioning and Water Heating	O	C	C	C	C	O	On	On	⊗
O = Damper is Open			C = Damper is Closed			⊗ = See MD-3 design Criteria			

ΔT Differential thermostat
 T_{ci} Temperature sensor collector inlet
 T_{co} Temperature sensor collector outlet
 T_s Temperature sensor rock bin storage
 T_w Temperature sensor water tank
 W_1 First stage of heat (solar)
 W_2 Second stage of heat (auxiliary)

MD-1 Motorized Dampers
 MD-2
 MD-3
 BD-1 Backdraft Dampers
 BD-2
 D-1 Manual Dampers
 D-2
 AHU Air Handling Unit

II. SOLAR ENERGY NOT AVAILABLE. When the differential between T_{CO} and T_{Ci} drops to 25°F or less the following takes place:

- A. The conventional space heating control circuit will: close MD-1; turn off air handler blower; turn off hot water pump (optional); open MD-2.
- B. First Stage Heating - demand for stored solar heat in space.
 - 1. When T_s sensor (heat storage box) is above 90°F, the conventional space heating control circuit will automatically bring on the auxiliary heating unit to ensure a minimum supply air temperature which will avoid the sensation of drafts. (Note: The heating system will still be circulating air through the heat storage unit to ensure all of the solar energy is used.)
- C. Second Stage Heating (same as I-C above).
- D. Third Stage Heating (same as I-D above) - heat pump only.

III. DOMESTIC WATER HEATING

- A. Winter operation permits domestic water to be preheated any time the system is storing heat. The sensor T_w will shut off the hot water pump when set point temperature of 140°F (can be adjusted) in the domestic water storage tank is reached.
- B. Summer operation permits the T_w sensor, when satisfied, to shut down the hot water pump and Solaron air handler and close MD-1 until water temperature in the storage tank drops 15°F below set point of T_w .

IV. AIR CONDITIONING

- A. Solar available: System preheats domestic water, auxiliary system cools space as demand is dictated by thermostat and MD-3 opens fully.
- B. Solar unavailable: Auxiliary system operates as in IV-A above and the solar air handler and domestic water pump are off.

HOW TO OPERATE YOUR SOLARON® SYSTEM

The Soloron system is simple to operate. All you have to do is set the thermostat to the desired temperature. The automatic control system will do the rest. We recommend that to obtain the most benefit from your solar system you reduce the thermostat temperature setting to 65°F (18°C) or less at night during the coldest period of the year when the storage will typically be depleted before morning. (Heat pump auxiliary units may be left at one temperature setting. Consult your heat pump supplier for setback information.)

For the rest of the year, to minimize auxiliary energy usage, the thermostat should not be set back at night. If it is reduced, the usage of backup fuel may actually be increased. The system is designed to turn on the auxiliary system when there is a two degree (or more) difference in the temperature of the heat space and the thermostat setting. Accordingly, when you increase the thermostat setting in the morning, the auxiliary heating system could be turned on even though there may still be sufficient heat (solar) in storage.

Winter - Summer Operation

Many solar systems have two operating cycles. The winter cycle is for heating your home and preheating the domestic hot water (if you selected this option). The summer cycle is only for preheating the domestic hot water. The system controller has a switch which is visible from the outside. You should move this switch to the desired operating cycle. The system controller is typically located in the mechanical room, near the air-moving equipment. **YOU DO NOT HAVE TO REMOVE THE COVER OF THE SYSTEM CONTROLLER TO MAKE THIS ADJUSTMENT.**

A typical system may also have one or more dampers which must be changed at the same time. See schematics on pages 13, 4, 5 and 6 for the location of these dampers D-1 and D-2. These dampers are generally manually operated. These dampers are not supplied by Soloron so you should have the installer explain how to operate the dampers he selected for your system. **IF THE DAMPER IS SET IMPROPERLY YOU MAY GET NO STORED HEAT IN THE WINTER WHEN YOU NEED IT OR YOU MAY STORE HEAT IN THE SUMMER WHEN YOU DO NOT NEED IT.** Some locations may require heat to be stored in the summer due to night heating needs.

Optional System Monitor

Your system may have an optional "System Monitor" which would typically be installed near the thermostat. Six operations are monitored and will indicate which functions of the system are operating. Typically the monitor will show the simultaneous operation of more than one function.



A light by these operations indicates the following functions.

- | | |
|--------------------|---|
| System On: | System is ready to operate. If this light is not on then check circuit breaker or fuse box. If the light still is not on then call serviceman. |
| Solar Collecting: | Power is being supplied to the solar air handler, the blower motor is operating and air is circulating through the collector. |
| Water Preheating: | Power is being supplied to the water pump and the domestic hot water preheat is operating. This operation will function only if you selected this option. |
| Solar Heating: | Solar heat is being supplied to the house. If solar collection light is also on then heat is being supplied directly by the collector; otherwise, heat is being supplied from storage. If auxiliary heating light is also on then the solar system is supplying part of heat requirement. |
| Auxiliary Heating: | Auxiliary heating system is operating. |
| Cooling: | This operates only if the house has conventional air conditioning. |

ROUTINE MAINTENANCE

The Solaron system requires only minimal upkeep for economical and long-lasting operation. We recommend that a qualified serviceman check the operation of the system twice a year. The system installer will either perform this service for you or will recommend a serviceman.

BE SURE TO DISCONNECT ELECTRICITY BEFORE SERVICING ANY ELECTRICAL COMPONENTS (controller, air handler, dampers, etc.).

The minimum maintenance requirements to be done are described below:

Solaron Air Handler Model AUO400 AND AUO500

Blower Motor

Visually check motor to confirm which type you have. DO NOT OVER-OIL.

Type 1 — Permanently sealed bearings - no oil required.



Type 2 — Motor with oil cups - oil twice a year (#20 S.A.E. non-detergent oil).

Blower Bearings

Permanently sealed - no oil required.

V-Belt

Check wear and tension, replace if necessary.



Solaron Motorized Dampers

Damper Motors

Oil twice a year (#10 S.A.E. non-detergent oil, similar to #465 Anderol or Goodlight #10 oil). DO NOT OVER-OIL.

Damper Linkage

Check play and tension of all push rods and arms. Check damper closing for tight seal. Readjust if needed. Oil (same as damper motor above).

Water Pump

The Grundfos circulation pump requires no oiling since it is water lubricated during normal operation. Your system will have a water pump only if the domestic water preheat option is selected.

Filters


These should be changed twice yearly or more often if conditions warrant. It is important that filters be clean if the system is to operate efficiently. New system owners should change filters after the first four weeks of operation.

STEPS TO FOLLOW TO OBTAIN MAXIMUM PERFORMANCE FROM YOUR SOLARON® SYSTEM

Estimates of system performance are typically based on average weather bureau data accumulated over many years. Yearly variations are to be expected because of changes such as solar radiation available, temperatures, wind conditions and living habits.

The amount of heat supplied by the solar system will vary by month. For example, a system designed to supply 60 percent of the ANNUAL heating requirement may supply only 25 percent in the coldest month of the year and virtually all the heating requirements in the spring, summer and fall. If a system is supplying only 25 percent of the heating requirement for a month, then most of the heat produced by the solar collector that month will be supplied directly to the heated space during the day and very little, if any, heat will be retained in storage for use at night.

CRITERIA FOR SELECTION OF THE ANNUAL FUEL SAVINGS PERCENTAGE



BUILDING SPACE HEATING

THE LOAD VARIES WITH THE TIME OF THE YEAR. THE SOLAR SYSTEM SHOULD NORMALLY BE SIZED TO PROVIDE 25% TO 75% OF THE YEARLY HEATING LOAD.

NOTE THE 100% SYSTEM HAS A LARGE AMOUNT OF NONUTILIZED ENERGY AND IS IMPRACTICAL & UNECONOMICAL.

To improve the effectiveness of your solar system you should do the following:

- Insulate your house. Consult local insulation suppliers for exact R value recommended for your area.
- Use double pane glass or storm windows.
- Remember that many fireplaces waste heat when they are in use.
- Keep fireplace dampers closed when not in use.
- Run exhaust fan for minimum time.
- Keep windows and doors closed during heating season.
- Set thermostat at maximum of 70°F (21°C) during day and maximum of 65°F (18°C) at night only during the coldest period of the year. See section on "How to Operate Your Solaron System" for a description of the problems of improper night setback.
- Caulk your house to minimize air leaks.
- Minimize usage of electrical, fuel oil and/or gas operated appliances. What may appear as fuel usage may also be increased usage of other appliances.
- Insulate the preheat water tank and hot water tank, if tanks are not supplied with adequate insulation.
- Insulate hot water lines.
- Note that the collectors are free from shading.

You should contact your serviceman only after concluding that you have done everything possible to conserve energy.

IF YOUR SOLARON® SYSTEM DOES NOT WORK


To obtain assistance you should:

- First, contact the system installer. If you do not know the company's name then call your builder.
- If your system installer should not be readily available, then contact any installer of Soloron equipment (see telephone Yellow Pages).
- If you need further assistance, contact the nearest Soloron distributor (see telephone Yellow Pages).
- Should all efforts to obtain local assistance not be successful, then contact:

Soloron® Corporation
300 Galleria Tower
720 So. Colorado Boulevard
Denver, Colorado 80222
Telephone (303) 759-0101

Due to Soloron®'s continuing policy of product improvement, products and specifications may change without notice.

AS BUILT DRAWINGS



SYSTEM SCHEMATIC

APPLIES TO SYSTEMS AT ALL BLDGS.
NO SCALE

SEQUENCE OF EVENTS							
O = OPEN C = CLOSED	MD1	MD2	MD3	MD4		BD1	BD2
MODE							
HEATING FROM COLLECTORS	O	C	C	O		O	O
HEATING FROM STORAGE	C	C	O	O		O	C
STORING HEAT	O	O	C	C		C	O

ORIGINAL PAGE IS
OF POOR QUALITY

FOLDOUT FRAME

SOLAR
HEATING
SYSTEM

QUAD
COMPLEX

SHELBY
OAKS
CORPORATE
PARK

As Built


BY: AT DISTRIBUTORS		
SCALE:	APPROVED BY:	DRAWN BY: L.G.
DATE: NOV 2, '77	FRED F. FARRIN, ENG.	REvised: 8/15/78
802 ROZELLE, MEMPHIS, TENN.		
(901) 278-7211		DRAWING NUMBER S-157-1

FOLDOUT FRAME

2




COLLECTOR
SCALE



GENERAL LAYOUT
SCALE 1/8" = 1'-0"

FOLDOUT FRAME


1



COLLECTOR ARRAY DUCTING DETAIL
SCALE 1/4" = 1'-0"

NOTE: ALL CONNECTIONS TO
COLLECTORS 10" Ø.


CONNECTING DUCTS TO
ROCK BOX AND AIR HANDLER
18/18



LAYOUT
8" = 1'-0"

MOTORIZED ZONE DAMPERS TO BE
OPENED WHEN ZONE REQUIRES
HEATING

ORIGINAL PAGE IS
OF POOR QUALITY



DETAIL MECHANICAL
EQUIPMENT ABOVE
ROCK STORAGE BOX SCALE 1/2" = 1'-0"

SOLAR HEATING SYSTEM

SCALE:	APPROVED BY:	DRAWN BY LG
DATE: JAN '78		REVISED 8/15/78
SHELBY OAKS CORP. PARK		
QUAD FOUR COMPLEX MEMPHIS, TENNESSEE		DRAWING NUMBER S-137-2 REV.

SOLAR POWERED EQUIPMENT

1. COLLECTOR PANELS (COORDINATE WITH SOLAR INSTALLATION MANUAL "SOLAR COLLECTOR")
COMPLETE WITH: A. KILS DOWN CLAMPS & BOLTS
B. TWO CAPS, FORT GASKETS
C. PERIMETER SEALANT TAPE
D. 1/2" PUMP: 75" & 33"
E. LENSES, WITH THE'S, X'S
AND EL'S.

2. SOLAR AIR HANDLING UNIT (COORDINATE WITH SOLAR INSTALLATION MANUAL "AIR HANDLING")
COMPLETE WITH: A. SPARKING DUCTS 1 - 5
(LENSES & MOTOR FACTORY
INSTALLED)
B. MOTOR, PULLEY & BELT
(FIELD INSTALLED)
C. MOTOR RELAY, OVERCLOCK
OR MAGNETIC STARTER
(FIELD SUPPLIED & IN-
STALLED)

3. SOLAR CONTROL PANEL (COORDINATE WITH SOLAR INSTALLATION MANUAL "CONTROLLER")
COMPLETE WITH: A. THREE SENSORS: T_{amb} , T_{col} , T_{gl}
B. 2-STAGE THERMOSTAT & SUB-
BASE.
C. 120V/24V TRANSFORMER
(FACTORY INSTALLED ON
PANEL)

SEE BACKSHEET DRAWING (COORDINATE TO SIDE &
SECTION WITH ENCL.)

GENERAL NOTES

DO NOT SCALE FROM DRAWING. SEE ALSO FOR EXACT
LAYOUT DIMENSIONS. THIS CONTRACTOR TO COOR-
DINATE MECHANICAL WORK WITH OTHER TRADES. NO
CHANGES THAT COULD AFFECT THE OPERATIONS OF
THE SOLAR & FURNACE SYSTEMS SHALL BE MADE
WITHOUT THE APPROVAL OF SOLAR.

DUCT INSULATION

- A. ALL SOLAR DUCTS USE EITHER OF THREE MINIMUM
INSULATION SPECIFICATIONS:
a. SUFFICIENT TO BE LINED WITH 1" THICK,
1-1/2" DENSITY, R-3.85 @ 75°F MIN.
ORANGE-CORNING TYPE 150 OR IN 1" LENS-
COFFIC OR EQUIVALENT.
b. FIBERGLASS DUCTS TO BE 1" THICK, R-4.36
@ 75°F MIN., ORANGE CORNING TYPE 4.75 FO
OR IN MICRO AIR W/THIN-LOC SAPS OR EQUIVA-
LENT.
c. UNINSULATED PROTECTED AREAS (ATTC, GABLE SPACE
AND SO EITHER OF ABOVE TYPES:
a. WRAP WITH 1-1/2" THICK, 1/4" DENSITY R-5.34
@ 75°F MIN., ORANGE-CORNING TYPE 150 OR
IN R-4.36, FIB-4 OR EQUIVALENT.
c. UNINSULATED UNPROTECTED AREAS (ROOF, GROUND),
USE IN LINE OF ANY OF ABOVE:
a. DUCT LINER BOARD, 2" THICK, R-8.75.
WEATHERPROOF AND SUPPORT AS FOR LOCAL
CODES.

ALL SOLAR DUCTWORK JOINTS TO BE SEALED AIR-
TIGHT WITH SCOTCH TAPE #723-11-CL SILICONE
SEALANT RATED AT 250°F. MIN. EQUIVALENT
PRODUCT ACCEPTABLE. DO NOT USE DUCT TAPE.

DUCTS INSTALLED IN DUCTWORK SHALL BE
SOLAR AIR TIGHT IN THE DUCT.

ALL SQUARE DUCT BLADES TO HAVE TURNING VANE.
AUXILIARY HEATING UNIT SHOV BE SUITABLE FOR
HEATING AIR TEMPERATURES OF 150 DEGREES F.

DUCTWORK SHALL BE INSTALLED IN ACCORDANCE
WITH GRACK. STANDARDS. SIZE SHALL BE 700 TO
500 FPM & BOUNDED @ 400 TO 500 FPM.
SUPPLY AIR SHALL BE SIZED IN ACCORDANCE WITH
SPE. RECOMMENDATION FOR FURNACE ROOM SIZE & VOLUME.
AIR SUPPLY: THROUGH R.A. CIRC. FROM ALL ROOMS
VIA A DUCTED R.A. SYSTEM OR UNFURNACE ROOM.

ALL DUCTWORK MIN. ON END ARE THINER THAN. SIZE
FIBERGLASS DUCTWORK CAN BE USED INSTANT IN AREAS
WHERE IT MAY BE SUBJECT TO ABUSE OR TRAFFIC.
DO NOT BE ABUSED.

CHANGING END ON PANEL. DUCT TO BE 4'-6" LONG

TO THE BEST OF OUR KNOWLEDGE AND
ABILITY, THIS LAYOUT, THE EQUIP-
MENT, AND ITS INSTALLATION COM-
PLIES WITH IMPS (SOLAR 4937) 2,
S-671 THROUGH S-671-12.

SEE EXCEPTION IN WRITE UP



COLLECTOR ARRAY DUCTING DETAIL

SCALE 1/4" = 1'-0"

BOTH ARRAYS THE SAME
ALL CONNECTIONS TO
COLLECTORS 10" Ø EXCEPT
AS NOTED.

ORIGINAL PAGE 17
OF POOR QUALITY

FOLDOUT FRAME

2

SOLAR HEATING SYSTEM		
SCALE	APPROVED BY	DRAWN BY LG
DATE: JAN. '78		REVISED 8/15/78
SHELBY OAKS CORP. PARK		
QUAD FOUR COMPLEX MEMPHIS, TENNESSEE		DRAWING NUMBER S-137-3, REV

NORTH

CARRIER
MODU-PAC

BLDG 1
DIMENSIONS SAME AS
BLDG 3

WEST

BLDG 4

CARRIER
MODU-PAC

BLDG 3

CARRIER
MODU-PAC


30'-0"

FOLDOUT FRAME

C-2

COLLECTOR
ALL DIMENSIONS

1
SAME AS



FOLDOUT FRAME

2

As Built

COLLECTOR ARRANGEMENT
ALL DIMENSIONS SHOWN ARE APPROX.

HEATING & A/C PLAN - SOLAR		
SCALE: 1" = 16'-0"	APPROVED BY:	DRAWN BY: L.G.
DATE: OCT 31, 77		REVISED
SHELBY OAKS CORPORATE PARK		
QUAD COMPLEX		DRAWING NUMBER S-137-4